Important Information:

All information contained in this drawing (including digital data) should be checked and verified prior to any fabrication or construction.

We advise that an arborologist be appointed to correctly determine the species and condition of all trees surveyed prior to any design work.

Survey Legend

FENCES

BARBED WIRE FENCE	B/W	Trees	
CORRUGATED IRON FENCE	CI		
CLOSE BOARD FENCE	C/B		
CHESTNUT PALING FENCE	C/P	Hedges	Privet 1:2
IRON RAILING FENCE	I/R		
POST AND CHAIN FENCE	P/C		
POST AND RAIL FENCE	P/R	Walls	Wall 2.0m (Width To Scale)
POST AND WIRE FENCE	P/W		
CHAIN LINK FENCE	C/L	Fences	C/B 1.8m
LARCH LAP FENCE	L/L		
INTERWOVEN FENCE	I/W		
WIRE MESH FENCE	W/M		

ABBREVIATIONS

BOLLARD	Bo	MARKER	Mk
BRITISH TELECOM IC	BT	NOTICE BOARD	NB
CONCRETE PAVING SLABS	CPS	PARKING METER	PM
COVER LEVEL	CL	ROAD NAME PLATE	RNP
DROP KERB	DK	ROAD SIGN	RS
ELECTRIC INSPECTION COVER	EC	RODDING EYE	RE
ELECTRICITY POLE	EP	RETAINING WALL	Rtw
FIRE HYDRANT	FH	RAINWATER PIPE	RWP
FLOWER BED	FB	STOP VALVE	SV
FOOTPATH	FP	TELEGRAPH POLE	TP
GAS VALVE	GV	TELEPHONE CALL BOX	TCB
GULLY	Gy	TRAFFIC LIGHT	TL
INSPECTION COVER	IC	UNABLE TO LIFT	UTL
PIPE INVERT LEVEL	IL	UNKNOWN	Unk
KERB OUTLET	KO	VENT PIPE	VP
MAN HOLE	MH	WATER METER	WM
THRESHOLD	TH	DIAMETER	Ø

Tree Schedule

Pt No	Spread	Bole	Height	Feature
2126	12	0.45	16	OAK
99	14	0.9	14	OAK
106	8	0.8	14	ASH
116	10	0.6	14	ASH
322	6	0.2	8	ELDER
324	6	0.6	10	ASH
325	6	0.5	10	ASH
326	8	0.8	12	ASH
327	8	0.6	14	ASH
328	6	0.7	14	ASH
329	6	0.3	10	ASH
334	8	0.5	10	ASH
416	4	0.4	11	ELDER
417	10	0.9	14	ASH
418	12	0.5	14	ASH
445	14	0.9	16	OAK
446	6	0.5	6	OAK
447	16	1.2	16	OAK
563	14	0.8	16	OAK
564	16	0.6	14	OAK
565	14	0.5	16	OAK
566	14	0.5	16	OAK
567	14	0.5	16	OAK
568	14	0.5	16	OAK
569	12	0.45	16	OAK
570	6	0.45	10	HOLLY
571	8	0.7	10	HOLLY
586	8	0.6	8	HAZEL
640	16	0.9	16	OAK
641	16	1	16	OAK
642	16	0.75	18	OAK
660	6	0.25	12	CHERRY
661	12	0.6	16	ASH
662	14	0.8	14	ASH
665	8	0.25	6	CHERRY
667	12	0.6	16	ASH
668	12	0.6	16	ASH
771	1	.075		SAPLING
772	1	.075		SAPLING
773	1	.075		SAPLING
10004	0.7			STUMP
10051	0.9			STUMP
10056	0.23			STUMP
10060	0.46			STUMP
10061	0.23			STUMP
10115	12	0.9	18	OAK
10116	0.4			STUMP
10117	0.3			STUMP
10250	1	.075		SAPLING
10261	16	0.9	24	OAK

North:

Grid: OS GPS

Levelling: GPS

Drawing Title:

Topographical Survey

Site Address:

Townhouse Farm
Church Lane
Ardingly
RH17 6UR

Client:

Balcombe Estate

Surveyor	MB	Drawn By	WB	Verified By	AF	Date	30.12.20

CM No: CM/20651/T

Rev:

Scale: 1:200m @ A0

Date: December 2020

Cadmap Ltd
Unit 131 Dunsfold Park
Cranleigh
Surrey, GU6 8TB
T: 01483 429385
E: info@cadmap.co.uk
W: www.cadmap.co.uk

worksafe consultant
Accredited Contractor
THE SURVEY ASSOCIATION
Constructionline