©2020 Cellnex
All rights reserved. No part of this publication may be reproduced, stored in a retrieval system or transmitted in any form or by any means (Electronic, Mechanical, Photocopying, Recording or otherwise), without the prior written consent of the Company.

POWER POLE

O/H POWER LINES

GRASS FIELD WITH APPROX 4° SLOPE

12m HIGH TREE

PROPOSED AREA TO BE RE-GRADED TO FORM STABLE SLOPE

GROUND LEVEL +1.0m

10000

PROPOSED 22.5m HIGH FLI ATS1301 LATTICE TOWER ON 6.25m x 6.25m RC FOUNDATION SUBJECT TO GI

PROPOSED 3No. GPS UNITS FIXED TO CABLE MANAGEMENT

PROPOSED 2.4m HIGH CHAINLINK FENCE TOPPED WITH 3 STRANDS OF BARBED WIRE FORMING 10m x 15m COMPOUND, C/W 1.0m WIDE ACCESS GATES

PROPOSED 12No. CABINETS ON 3.7m x 6.9m CONCRETE BASE

PROPOSED 600mm WIDE HORIZONTAL CABLE LADDER ON 8No. NEW SUPPORT POLES FIXED TO NEW FOUNDATIONS

PROPOSED SHARED METER CABINET WITHIN FENCELINE ON CONCRETE BASE. METER CABINET C/W 4No. PAVING 600mm SLABS TO THE FRONT

15000

BRAMBLES & BUSHES

GROUND LEVEL 0.0m

RAILWAY 2m BGL

EXISTING 1.4m HIGH CONCRETE POST & WIRE FENCE

12-13m HIGH TREEs

N

0 1m 5m 10m

NOTES

UNDERGROUND SERVICES

UNDERGROUND SERVICES ARE INDICATIVE ONLY. POSITIONS SHOULD BE CONFIRMED ON SITE PRIOR TO ANY DEVELOPMENT

DRAINAGE
DUCTS
FEEDERS
FENCE PLAN
GAS
LIGHTNING PROTECTION - EARTHING
POWER
SERVICES UNKNOWN
TELECOMS
WATER

ACCESS ARRANGEMENTS

KEYS:-

ARQIVA GATE KEY	1
B KEY	2
C KEY	3
LEGGE KEY	4

SURVEY REQUIRED TO CONFIRM ACCESS KEYS FOR REMAINING ROOMS AND SITE ENTRANCE

CELL No. S5_11e

ISS	REVISION	DATE	DRN	APP
4	COL.MOD.UK.0002684 BNG REMOVED	06/05/25	CIR	CIR
3	COL.MOD.UK.0002684 PLANNING AMENDS	31/10/24	CIR	CIR
2	COL.MOD.UK.0002684 COMPOUND MOVED	23/03/23	RST	MK
1	PLANNING	27/04/22	RTL	RST

cellnex
driving telecom connectivity
CELLNEX UK
R+, 4TH FLOOR, 2 BLAGRAVE STREET, READING, RG1 1AZ
Tel. 020 4526 8553

SITE No S5-11
LAND ADJACENT TO ROCKY LANE
ARABLE FIELD ADJACENT TO ROCKY LANE
SANDROCKS
ANSTY AND STAPLEFIELD
RH16 4TW

NGR TQ 32514 22168
OS GRID 532514 122168

TITLE
SITE PLAN
PROPOSED

SCALE 1:200

DRAWN	GV	31/03/22
APPROVED	CIR	06/05/25

DRG No. S5-11-00-001-MD004
Sheet 1 of 1
Rev 4

A3