



Given the small scale of the project and the limited scope of works, dedicated tree protection fencing is not considered necessary. No heavy machinery or excavation is required within proximity of the retained trees, and all activity can be managed to remain outside their Root Protection Areas. The nature of the works means that standard site discipline will be sufficient to avoid encroachment, with no foreseeable risk of accidental damage to stems, canopies, or underlying roots.

No excavation is required near any of the retained trees, and the works can be undertaken without entering or disturbing their RPAs.

If the scope of works changes, or if any activity is proposed that may require machinery, excavation, or access within or near the RPAs, the arboricultural consultant must be contacted prior to commencement so that appropriate protection measures can be reviewed and agreed.



Tel.07759482934

www.absolutearb.com

Site: 39 Oathall Road, Haywards Heath	1:200 at A2
Drawing Title: Tree Protection Plan	September 2026

Key:

● Category A

● Category B

● Category C

● Category U

▨ Existing Hardstanding

Category

Root Protection Area

Crown Spread

Tree Number

NOTE: All tree/group numbers have approximate locations.