

Impact Schedule

Tree number	Species (common/botanical)	Stem diameter (mm)	Height (nearest m >10m)	Crown spread (nearest 1/2m)	Crown clearance (m)	Life stage	Category	RPA radius (m)	Landscaping - Impact on Trees	Buildings - Impact on Trees	Mitigation
TG3	Birch/Betula pendula	440 largest	18	6m max	1	EM	B2	Largest 5.2	No impact	No impact	Protect in accordance with BS 5837
TG4	Birch/Betula pendula	120 largest	17	3	2	EM	B2	2	No impact	No impact	Protect in accordance with BS 5837
TG5	Birch/Betula pendula	460 largest	17	4.3	1	EM	B2	Largest 6	No impact - existing hard surfacing to remain	No impact	Protect in accordance with BS 5837
TG6	Italian alder/Alnus cordata	430 largest	18	6	1	M	C2 elder, B2 birch	Largest 4.6	No impact	No impact	Protect in accordance with BS 5837
TG7	Birch/Betula pendula	400, 400	17	6	1	EM	B2	4.8	No impact	No impact	Protect in accordance with BS 5837
T28	Oak/Quercus robur	200	10	3.3	2	EM	A1	2.4	No impact	No impact	Protect in accordance with BS 5837
TG29	Oak/Quercus robur	450 & 200	12	3.3	2	EM	A2	5.4	No impact - existing hard surfacing to remain	No impact	Protect in accordance with BS 5837
T30	Horn Oak/Quercus flex	300	10	4	2	EM	B2	3.6	No impact - existing hard surfacing to remain	No impact	Protect in accordance with BS 5837
T31	Oak/Quercus robur	300	10	4	2	EM	A2	3.6	No impact - existing hard surfacing to remain	No impact	Protect in accordance with BS 5837
T32	Oak/Quercus robur	1400	12	6	2	M	A3	15	No impact - existing hard surfacing to remain	2% incursion over areas of existing hard landscaping	Root foundations using existing sub-bases, drainage and services to be hand dig/undercut
T33	Oak/Quercus robur	800	20	1	3	M	A2	9.6	No impact	No impact	Protect in accordance with BS 5837
T34	Douglas fir/Pseudotsuga menziesii	550	22	2.3	10	M/OM	C2	6.6	No impact	No impact	Protect in accordance with BS 5837
T35	Oak/Quercus robur	700	18	7	2	M	A2	8.4	No impact	No impact	Protect in accordance with BS 5837
T36	Oak/Quercus robur	820	18	1	3	M	A2	9.8	No impact	No impact	Protect in accordance with BS 5837
T37	Birch/Betula pendula	200 & 220	18	3	3	M	C2	2.4	No impact	No impact	Protect in accordance with BS 5837
T38	Oak/Quercus robur	1130	17	6	4 over near, 10 over stable	M	A2	13.6	No impact - existing hard surfacing to remain	8% incursion over areas of existing hard landscaping	Root foundations using existing sub-bases, drainage and services to be hand dig/undercut
T39	Oak/Quercus robur	850	15	6	5	M	A2	10.2	No impact	No impact	Protect in accordance with BS 5837

[illegible]