12No Abelia x grandiflora 30%
8No Achillea 'Terracotta' 20%
8No Gaura lindheimeri 20%
4No Sambucus nigra 'Black Beauty' 10%
8No Stipa tenuissima 'Pony Tails' 20%

11No Euonymus fortunei 'Silver Queen'

33No Escallonia 'Apple Blossom'

1No Carpinus betulus 'Frans Fontaine'

1No Ligustrum lucidum

33No Escallonia 'Apple Blossom'

16No Viburnum tinus 'Eve Price'

2No Cornus kousa chinensis

13No Viburnum tinus 'Eve Price'

396No Carpinus betulus

10No Cornus alba 'Elegantissima'

8No Calamagrostis x acutiflora 'Karl Foerster' 10%
17No Sarcococca confusa 20%
34No Lonicera pileata 'Loughgall Evergreen' 40%
17No Skimmia japonica 'Rubella' 20%
8No Euonymus fortunei 'Dart's Blanket' 10%

17No Cornus alba 'Elegantissima'

2No Carpinus betulus 'Frans Fontaine'

2No Pyrus calleryana 'Chanticleer'

53No Escallonia 'Apple Blossom'

116-127

128

129

130

131

132

England Netball - Netball Court
30.50x15.25m with 3.05m runoff to all sides (stand alone court)
4.00m combined run off required between courts
England Netball - Netball Court
28.42x15.25m with 3.05m runoff to sides and 6.40m run back area (stand alone court)
28x15m overall with 3.05m runoff to sides and ends
4.10m run off required between courts

soccer U7 and U8 (5v5)
yards with 3 yard runoff
goal

2No Malus baccata 'street P

104No Prunus lusitanica

109No Prunus lusitanica

1No Camellia japonica

193

4No Euonymus fortunei 'Silver Queen'
4No Sarcococca humilis
5No Skimmia japonica 'Fragrans'

5No Viburnum davidii
1No Bergenia cordifolia 'Purpurea'
4No Berberis darwinii
4No Abelia grandiflora 'Kaleidoscope'

194

195

27No Prunus lusitanica

50No Prunus lusitanica

3No Abelia grandiflora 'Kaleidoscope'
3No Hebe 'Sapphire'
3No Berberis darwinii
15No Prunus lusitanica

26No Prunus lusitanica

7No Euonymus fortunei 'Emerald Gaiety'

2No Salvia greggii 'Peach'
3No Hebe 'Sapphire'

3No Pittosporum tenuifolium 'Golf Ball'
27No Prunus lusitanica

7No Pennisetum alopecuroides 'Hameln'
7No Skimmia japonica 'Fragrans'

196

197

13No Prunus lusitanica
1No Bergenia cordifolia 'Purpurea'

7No Pennisetum alopecuroides 'Hameln'

6No Viburnum

7No Sarcococca humilis
27No Prunus lusitanica

3No Pittosporum tenuifolium 'Golf Ball'
35No Prunus lusitanica
3No Abelia grandiflora 'Kaleidoscope'
3No Salvia greggii 'Peach'
3No Hebe 'Sapphire'
1No Bergenia cordifolia 'Purpurea'
13No Prunus lusitanica

198

7No Viburnum tinus 'Eve Price'
1No Amelanchier arborea 'Robin Hill'
5No Euonymus fortunei 'Emerald Gaiety'
55No Prunus lusitanica

00001
00002
00003
00004
00005
00006
00007
00008
00009
00010

SPECIFICATION
All works generally, to comply with the written Soft Landscape Specification. Any conflicting information to be brought to the attention of ACD Environmental before works commence on site.

NOTES:
DO NOT SCALE FROM DRAWING, ALWAYS SCALE FROM NOTED DIMENSIONS.

Drawing status : FOR INFORMATION

Legend

- Existing trees to be retained and protected during construction
- Proposed tree planting within hard landscape. See detail on sheet 2.
- Proposed tree planting within soft landscape. See detail on sheet 2
- Proposed specimen shrub planting to receive short angular staking on half standards with expandable tree ties. Irrigation tubing to root system as required
- Proposed climbing plants to be trained up adjacent wall/ fence/pergola with galvanised wires and hook set 250mm apart with support canes removed prior to planting
- Proposed hedge planting to be planted in a double staggered row 400mm apart and at 300mm centres in each row. To be maintained at 1m height
- Proposed shrub planting to receive 75mm bark mulch after planting operations
- Proposed grass areas to receive good quality amenity grass turves laid in line with good horticultural practices
- Proposed meadow mix, to be seeded with EM4 meadow mixture for clay soils supplied by Emorsgate Seed and sown at 4 grams per msq, or equivalent
- Proposed Flowering Lawn, to be seeded with EL1 Flowering lawn mixture as supplied by Emorsgate Seed and sown at 4 grams per msq, or equivalent
- Proposed wet tolerant meadow mixture, to be seeded with EM8 seed mix as supplied by Emorsgate Seeds and sown at 4 grams per msq, or equivalent
- Proposed grass area, to be seeded with A24 Wear and Tear grass seed mix as supplied by Germinal Seeds and sown at 50 grams per msq, or similar and approved
- Raised beds. Refer to hard landscape for details
- Play mounds
- Log steps from Playdale or similar
- Proposed public art
- Proposed storage tank. Refer to engineers details
- 18m³ Approximate soil volume required for tree in hard landscape. To be conformed by supplier of root cells which suit conditions.
- Bird Box - Swift bricks/boxes (20-30 to be installed in clusters of 3-5 units. Elevations of new build properties at minimum 5m height, away from direct sun. Integrated to building is preferred over mounted boxes.
- Dormouse nest boxes/tubes to be installed along Hedgerow H1. (8-15 features across the woodland, 20m spacing).
- Cut lines
- Planting Schedule on Sheet 00010
- Refer to hard landscape drawing HILL25205 12 for street furniture details.

Rev	Date	Details	Drawn

ACD ENVIRONMENTAL
Arboriculture
Archaeology
Ecology
Landscape Architecture
Phone: 01666 825646
Email: mail@acdenv.co.uk
Web: www.acdenvironmental.co.uk

project: Northern Arc, Burgess Hill Phase 1C, Eastern Neighbourhood Centre
client: Hill Partnerships Ltd
drawing: Soft Landscape Proposals
purpose: planning
date: May 2026
scale: 1:200@A1
drawing no: HILL25205 11
Sheet 00005
drawn: LS checked: DKM

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted. 2011. Copyright of this plan remains with ACD until all fees have been paid in full.