

Planting Specification

Drawing No. 1033-PSP-01
Date 2023.09.11
Project Name: BORDE HILL -
Address: Borde Hill Garden
Borde Hill Lane
Haywards Heath

Anna-Marie Powell
G A R D E N S

The Old Tractor Shed, Heath Farm,
Heath Road East, Petersfield,
Hampshire GU31 4HT

Delivery Notes:

RH16 1XP

Date	Rev. No.	Details
------	----------	---------

GENERAL SPECIFICATION

B1 SUPPLY

Contractor to supply compost, mulch, feed and all climbing and tree supports.
All plants to be supplied by AMPG. Contractor to allow for offload of all plants on delivery to a location/s near the planting bed/s, or as agreed with AMPG.

B2 EXISTING LAWN

All existing lawn should be made good when works have been completed.
Note: lawn edge to be cut vertically for aesthetic and stability

B3 NEW TURF LAWN

B3.1 Standards:

Turf to comply with the TGA (Turfgrass Growers Association) standards and BS3969.

B3.2 Preparation for turfing:

Remove all weeds, rubbish and stones over 30mm in diameter

Cultivate topsoil to a minimum depth of 100mm. reduce top 30mm to a fine tilth, if soil is clay or heavy loam - work in coarse sand to the top 50-75mm of topsoil at a ratio of 2:1. rake the soil level and firm the surface.

B3.3 Laying turf:

Transport turf over close butted timber planks. Lay turf in consecutive rows. Lay turf from timber planks protecting previously laid turf. Lay turf close butted breaking the joint in alternate rows. Use only whole turfs at margins. Consolidate lightly with wooden beaters. Brush in finely sieved topsoil to fill all joints. Peg turves with wooden pegs on slopes exceeding 30°. Ensure final surface is 20mm above any adjacent hard surface.

B3.4 Turfing adjacent to obstructions:

Leave a neat 300mm radius of soil round all newly planted trees. Unless otherwise shown on the drawing, turf right up to existing established trees, walls, fences and similar obstructions, leaving this area to be mulched, with no soil uncovered.

B3.5 Finish/Maintenance of new turf:

Spread and brush in a top dressing of fine sieved topsoil and sand 50:50 to fill any cracks and depressions.

Note: lawn edge to be cut vertically

B4 WILDFLOWER MEADOW - MEADOWSCAPE PRO

Prepare ground around existing trees and level, ensuring that the area has been de-compacted and raked over, removing all builders' rubble and items above 50mm diameter. All existing plant life and organic matter is to be removed from the wildflower areas and the correct grading and levels achieved before the application of Meadowscape Pro. Lay to suppliers' recommendations, 1m³ bulk bag is required to cover 40m² when laid at the recommended depth of 25mm