C grade tree to be removed	

Trees to be removed
Trees No.
T16
T17

B grade tree to be removed	

Trees to be removed
Trees No.
T14
T15

Legend:

Canopies of trees to be pruned:	

Notes	
Revisions	

Trunk of a category U tree
Those in such a condition that they cannot realistically be retained as living trees in the context of the current land use for longer than10 years

Trunk of a category A tree
Trees of high quality with an estimated remaining life expectancy of at least 40 years

Trunk of a category B tree
Trees of moderate quality with an estimated remaining life expectancy of at least 20 years

Trunk of a category C tree
Trees of low quality with an estimated remaining life expectancy of at least 10 years, or young trees with a stem diameter below 150mm

Canopy edge

1 ——— Tree no.
Ash ——— Tree species

0 2 4 6 8 10 20m
1:500 Scale

GRS
ARBORICULTURAL CONSULTANT LTD

GRS Arboricultural Consultant Ltd
The Old Coach House,
Waterside Mews,
Wateringbury,
Kent, ME18 5AB

Tel: 01622 817516
Email: guy@grstrees.co.uk
www.grstrees.co.uk

Please ensure all dimensions on site and any if there are any discrepancies please notify us.

© GRS Arboricultural Consultant Ltd 2025
The origin of this drawing was produced in colour - a monochrome copy should not be relied upon.

Material within this report including text and images, is protected by copyright. It may not be copied, reproduced, republished, downloaded, posted, broadcast or transmitted in any way except for your own personal and non-commercial use. Prior written consent from the copyright holder must be obtained for any other use of material. Copyright in all materials and/or works comprising or contained within this report remains with GRS Arboricultural Consultant and any other copyright owner(s) as specified. No part of this report may be distributed or copied for any commercial purpose.

Client	London Town Property Holdings Ltd
Title	Tree Managementl Plan - TMP-01
Site	Bolney Grange Business Park, Stairbridge Lane, Bolney, Haywards Heath, RH17 5PA
Date	01/12/2025
Drawn	GRS
Job ref	GRS.155.25
Scale	1:500
Paper size	A3
Drawing reference	240926-16330b-22

Trees That Need Removing To Accommodate Widening

c.37 metres of understorey to be removed


T2, T4, T5, T6,T7, T8, T9 T11 to be crown lifted retained trees to leave 5-6 metre clearance over the road

H18C2 Hawthorn & Blackthorn
T17C12 Field maple
37.4m
T16C12 Field maple
T15B12 Common Oak
T14B12 Common Oak
T13B12 Common Oak
T12C12 Field maple
T11C12 Ash
T10B12 Common Oak
T9C12 Ash
T8C12 Ash
T7C12 Field maple
T6C12 Ash
T5C12 Ash
T4C1 Ash
T3B1 Common
T2C12 Common
T1B1 Common Oak

7.10
8.24
8.14
8.03
9.40

11
10
9





GRASS
TARMAC
JOB'S LANE
TARMAC
Overhead Cable
Dilapidated Post & Wire Ht.1.5