

From: planninginfo@midsussex.gov.uk <planninginfo@midsussex.gov.uk>
Sent: 20 January 2025 12:05:32 UTC+00:00
To: "planninginfo" <planninginfo@midsussex.gov.uk>
Subject: Mid Sussex DC - Online Register - Consultee Comments for Planning Application
DM/25/0034

Consultee comments

Dear Sir/Madam,

A consultee has commented on a Planning Application. A summary of the comments is provided below.

Comments were submitted at 20/01/2025 12:05 PM from Oliver Benson on behalf of Environmental Protection.

Application Summary

Reference:	DM/25/0034
Address:	Workshop And Garages North Road Haywards Heath West Sussex RH16 3NJ
Proposal:	Discharge of condition on 8 of planning appeal AP/21/0034 (DM/20/1470).
Case Officer:	Rachel Richardson

[Click for further information](#)

Comments Details

Comments: I have reviewed the Stage 4 Validation Report concerning the remediation measures for the presence of PAHs. The original remediation statement specified that all gardens would require a 600mm cover system, involving the removal of existing soil, installation of a geo-textile membrane, and placement of clean soil. The remediation report also stated that it would be confirmed if barrier pipping was required.

The validation report indicates the following:

- The appendix contains four photos of several planters with a 600mm depth have been installed.
- Waste transfer notes confirm the removal of contaminated soil.
- Testing results for the clean soil brought to the site have been provided.
- There is a statement in the report that barrier piping was deemed unnecessary.

To ensure comprehensive compliance with the remediation

requirements, I request the following clarifications and additional evidence:

1. Barrier Piping Confirmation:

- Please provide confirmation from the water company that barrier piping was not required for this project.

2. Garden Construction Details:

- Were all gardens constructed using planters with a 600mm depth? If not, please provide additional photographs or documentation to confirm that all garden areas for the six properties were excavated to the required 600mm depth.

3. Geo-Textile Membrane Installation:

- There are no photographs showing the installation of the geo-textile membrane. Is the author of the validation report satisfied that there is sufficient evidence to confirm the membrane was properly installed?

These clarifications and additional evidence are necessary to ensure that the remediation measures have been fully and effectively implemented, and will allow me to make a recommendation on whether condition 8 should be discharged.

Kind regards