

LEGEND - 1:250

General

Red Line Boundary.

Buildings.

Existing Nursery Boundary Wall.
To be retained and protected.

Proposed Boundary Wall.

Relocation Existing Gate.
Gate to be repositioned within the opening formed by the removal of the existing blockwork wall.

Existing Routes & Surfaces

Gravel Path
To be retained and blinded with new dressing.

Resin Bound Gravel Service Route & Nursery Entrance.
Existing surface to receive bitmac overlay / remedial repairs and resin bound gravel overlay.

Existing Footpath.
To be retained.

Proposed Routes & Surfaces

Main Accessible Paths.
Firm, resin bound gravel to match existing, connecting the main play areas and landscape spaces.

Informal Gravel Paths.
More informal secondary paths encouraging exploration and alternative routes through the landscape.

Informal Gravel Adjacent To Nursery Entrance.
New gravel surfacing to replace existing grass and concrete to Nursery entrance.

Informal Gravel
Occasional mobile vending handstanding (partially existing / partially no dig).

Bark Play Safety Mulch.
Natural bark safety surfacing beneath selected play equipment.

Rubber Play Safety Surface.
Firm and accessible safety surfacing to selected play areas and connections, using a subtle 80% dark brown and 20% beige colour blend.

Reinforced Grass.
Natural grass strengthened in areas likely to experience heavier footfall and wear.

Grass Safety Matting.
Heavy-duty impact-attenuating grass safety matting.

Structures and

Landscape Features.

Stone Steps and Handrails.
Sandstone steps integrated into primary stepped path, with understated steel handrails.

Timber Steps and Handrails.
Sandstone steps integrated into primary stepped path, with understated steel handrails.

Timber Boardwalk.
Rustic timber platform providing access across sensitive ground and the gill landscape. Low rope edges supported by irregular natural robinia timber post upstands.

Natural Play Boulders.
Large natural boulders for informal play, balancing and seating. Potential to reuse suitable stone from the Asian Heath Garden as part of future works.

Rustic Tree Trunk Seating.
Simple informal seating using natural tree trunks positioned within play and planted areas.

Oak Picnic Tables and Benches.
Robust oak picnic furniture for families and groups, including accessible provision connected to firm paths.

Bespoke Curved Timber Bench.
Integrated into the edge of planting borders.

Gabion Retaining Wall.

Timber Litter Bin.

Proposed Native Meadow Seeding.
Species-rich native grass and wildflower seed mix appropriate to site conditions.

Proposed Hard Wearing Amenity Grass Seeding.
Hard-wearing grass seed mix for general recreation and informal landscape use.

Soft Landscape Layout.

Existing Trees.
Existing tree canopy (to be retained and protected in accordance with BS 5837). Canopy extent shown is approximate, based on the topographical survey; tree not surveyed by an arborist.

Tree Survey Extent.
Extent of Tree Survey undertaken by Tree Amigos, refer to report for details.

Existing Tree Canopy.
(Tree to be retained and protected in accordance with BS5837, Refer to Tree Amigos report).

Existing Trees - Partial Retention and Removal.
Selected existing trees retained for screening and landscape structure, with inappropriate species removed as part of the proposals.

2

Existing Shrub Vegetation To Be Managed.

Selective clearance of existing laurel and other inappropriate shrub vegetation to open up the landscape and create opportunities for new High Weald species planting.

Proposed Ornamental Grasses, Shrubs, And Herbaceous Planting.
Naturalistic matrix planting of grasses and flowering perennials appropriate to the planting character area.

Native Structure Mix.
Native shrub species to provide dense thicket.

Proposed Shrub, Herbaceous & Fern Planting.
Dense planting and drifts of ferns appropriate to shaded areas & woodland edges.

Proposed Hedge.
High Weald native hedge mix.

Proposed Climbers.
Climbing plants to walls or independent support structures where shown.

Grass Seating Area.

Proposed Trees & Planting

1 Meadow Landscape Transition.
Species rich meadow providing an informal setting for play and a transition to the wider landscape.

2 Meadow-Edge Ornamental Planting.
Naturalistic grasses, perennials and shrubs extending the character of the meadow into the play landscape.

3 Transitional Planting.
Mixed planting creating a gradual transition between the ornamental meadow character and more native planting.

4 Native Woodland-Edge Planting.
Layered native trees, shrubs and ground planting creating a natural transition into the surrounding landscape.

5 Native Buffer and Screening Planting.
Denser native planting providing enclosure, screening and habitat.

6 Wall Screening Planting.
Climbers to soften the existing blockwork wall, with native shrubs planted in front where space allows.

Semi-Mature Trees.
Trees providing immediate height, canopy structure and landscape presence.

Extra Heavy Standard Trees.
Trees providing intermediate scale and reinforcing the wider tree framework.

Feathered Trees.
Natural form trees planted with branches close to ground level to create a layered woodland character.

Multi-Stem Shrubs and Small Trees.
Natural form trees planted with branches close to ground level to create a layered woodland character.

Play Landscape Areas

1 Grass Amphitheatre.
Simple grassed terraces and slopes providing informal seating, gathering and play.

2 Toddler and Family Play Area.
An accessible and easily supervised play space with smaller scale climbing, swinging and sensory play.

3 Low-Level Natural Play Area.
Informal play using timber, stone, landform and natural materials to encourage exploration and unstructured play.

4 Senior / Big Play Area.
Larger-scale and more challenging play incorporating climbing, balancing, movement and elevated play.

5 Adventure Play Area.
A sequence of more challenging physical play experiences and alternative routes through the landscape.

6 Sensory and Quiet Play Area.
Smaller, sheltered spaces for sensory discovery, quieter play, seating and retreat.

7 Gill Natural Play Area.
Light-touch play and exploration focused around the existing gill landscape.

8 Lookout.
An accessible landscape destination providing elevated views across the wider High Weald landscape.

9 Hammock.
Hammock play for resting, swinging and quieter play. 1 hammock connected directly to the main accessible path by firm safety surfacing.

1544_WAKEHURST PLAY PROJECT

Kew Wakehurst

General Arrangement Plan

1544_100

1:250 @ A1

Rev A

09.07.26

RH17 6TN

Drawing Issue Status

☐ Comment/ Approval
☐ Contract
☐ Costing
☐ Construction
☒ Planning
☐ Record Dwg
☐ Tender
☐ BIM

© Copyright and all intellectual property rights remain vested in Southern Green Ltd

SouthernGreen

0191 440 0034
www.southerngreen.co.uk
studio@southerngreen.co.uk

Rev	Description	By	Chk	Date
--	First Issue	EV	LH	09.07.26
A	Updated following design team feedback - Planning Issue.	EV	LH	17.07.26

NOTES - IF IN DOUBT, ASK


- Do not scale directly from this drawing.
- All dimensions are in millimetres.
- All levels are shown in metres Above Ordnance Datum (AOD).
- All levels and dimensions are to be checked on site by the site manager/contractor prior to commencing any works or ordering any materials.
- This drawing is to be viewed in conjunction with all other detailed drawings and specifications from all members of the design team.
- Any conflicts/discrepancies are to be highlighted to Southern Green prior to commencing works or ordering any materials.
- All products and materials shown on this drawing, are to be provided as spotted or as 'equal and approved' by the client/ design team.

CDM - SAFETY, HEALTH & ENVIRONMENTAL INFORMATION

Principal Designer: **Studio Hardie**
In addition to the hazards/ risks normally associated with the types of work detailed on this drawing, note the following project specific risks which require attention/ mitigation by the contractor undertaking the works:

Construction: Working on a stopped site, unidentified below ground constraints and services.
Maintenance/ Cleaning: Same as above.
Decommissioning/ Demolition: Same as above.

It is assumed that all works will be carried out by a competent contractor, working where appropriate, to their own approved method statement. This is not an exhaustive list and reference must be made to the Construction Phase Plan or Health and Safety File and any additional Risk Assessment documents available.



Scale Bar - 1:250 @ A1
0m 1m 2m 3m