Planting Schedule: Ornamental

Shrubs

Abbreviation	Species	Pot Size	Specification	Density	Qty.
Abe_grand 'FM'	Abelia x grandiflora 'Francis Mason'	3L	Bushy; 3 brks; C	3/m²	164 No.
Ceap_arb 'TB'	Ceanothus arboreus 'Trewithen Blue'	10L	Cared; Leader with Laterals; 5 brks; C	1/m²	8 No.
Cera_wil	Ceratostigma willmottianum	3L	Bushy; 4 brks; C	4/m²	317 No.
Cist_SP'	Cistus 'Silver Pink'	3L	Bushy; 4 brks; C	4/m²	192 No.
Cist_corb	Cistus x corbariensis	3L	Bushy; 4 breaks	4/m²	549 No.
Cod 10'	Codiaus 'Crasvi'	10L	Branched; 5 brks; C	1/m²	2 No.
Daph_odo 'A'	Daphne odora 'Aureomarginata'	5L	Branched; 5 brks; C	3/m²	182 No.
Esc_fol'	Escallonia 'Apple Blossom'	5L	Bushy; 4 brks; C	3/m²	77 No.
Hebe_'WC'	Hebe 'Wiri Charm'	3L	Bushy; 5 brks; C	4/m²	126 No.
Hebe_rak	Hebe rakaiensis	3L	Bushy; 5 brks; C	4/m²	594 No.
Hydra_'LW'	Hydrangea macrophylla 'Lanarth White'	5L	Branched; 5 brks; C	2/m²	89 No.
Hydra_'MME'	Hydrangea macrophylla 'MME Mouillier'	5L	30-40cm ht; SL; Branched; 5 breaks	2/m²	183 No.
Hyd_quer 'SQ'	Hydrangea quercifolia 'Snow Queen	10L	Specimen; C	1/m²	10 No.
Lava_ang 'Hid'	Lavandula angustifolia 'Hidcote'	3L	Bushy; 5 brks; C	5/m²	1053 No.
Lon_pil	Lonicera pileata	2L	Bushy; 3 brks; C	4/m²	65 No.
Maho_aqui	Mahonia aquifolium	5-7.5L	Branched; 3 brks; C	3/m²	117 No.
Osma_burk	Osmanthus x burkwoodii	5-7.5L	Bushy; 5 brks; C	2/m²	10 No.
Phil_'BE'	Philadelphus 'Belle Etoile'	3L	Branched; 4 brks; C	3/m²	327 No.
Ribe_sang	Ribes sanguineum	10L	Branched; 7 brks; C	1/m²	4 No.
Rosm._'MJJ'	Rosmarinus officinalis 'Miss Jessopp's Upright'	2L	CG	4/m²	387 No.
Sarc_humi	Sarcococca humilis	2L	Bushy; 4 brks; C	5/m²	96 No.
Skim_conf 'KG'	Skimmia x confusa 'Kew Green'	3L	Bushy; 3 brks; C	4/m²	551 No.
Vibu_bodn 'D'	Viburnum bodnantense 'Dawn'	10L	Branched; 4 brks; C	1/m²	4 No.
Vibu_davi	Viburnum davidii	3L	Bushy; 3 brks; C	4/m²	29 No.
Vinc_min 'A'	Vinca minor 'Alba'	2L	Several Shoots; 3 brks; C	5/m²	144 No.

Herbaceous

Abbreviation	Species	Pot Size	Specification	Density	Qty.
Achi_'CG'	Achillea 'Coronation Gold'	2L	Full Pot; C	4/m²	438 No.
Alch_moll	Alchemilla mollis	3L	Full Pot; C	5/m²	639 No.
Anem._'H.J.'	Anemone x hybrida 'Honorine Jobert'	3L	Full Pot; C	4/m²	460 No.
Aspl_scol	Asplenium scolopendrium	3L	Full Pot; C	3/m²	55 No.
Berg_cord	Bergenia cordifolia	2L	Full Pot; C	5/m²	280 No.
Core_grand 'S'	Coreopsis grandiflora 'Sunray'	3L	Full Pot; C	4/m²	388 No.
Gali_odo	Galium odoratum	2L	Full Pot; C	4/m²	184 No.
Gera_'B'	Geranium 'Brookside'	2L	Full Pot; C	4/m²	14 No.
Gera_endr	Geranium endressii	2L	Full Pot; C	6/m²	4 No.
Gera_macro	Geranium macrorrhizum	2L	Full Pot; C	6/m²	75 No.
Heuc_'KLP'	Heuchera 'Key Lime Pie'	2L	Full Pot; C	5/m²	5 No.
Heuc_cyn' 'G'	Heuchera cylindrica 'Greenfinch'	3L	Full Pot; C	5/m²	99 No.
Lir_muac	Liriope muscari	2L	Full Pot; C	6/m²	104 No.
Luzu_niv	Luzula nivea	3L	Full Pot; C	5/m²	438 No.
Lyth_sali	Lythrum salicaria	3-4L	Full Pot; C	4/m²	300 No.
Nep_nepa	Nepeta racemosa	3L	Full Pot; C	4/m²	262 No.
Pote_frut 'A'	Potentilla fruticosa 'Abbotswood'	3L	Bushy; 4 brks; C	4/m²	555 No.
Pulm_off 'SW'	Pulmonaria officinalis 'Sissinghurst White'	2L	Full Pot; C	5/m²	763 No.
Sang_off 'T'	Sanguisorba officinalis 'Tanna'	3L	Full Pot; C	5/m²	274 No.
Tell_grand	Tellima grandiflora	2L	Full Pot; C	4/m²	487 No.
Verb_bon	Verbena bonariensis	3L	Full Pot; C	3/m²	307 No.

Grasses

Abbreviation	Species	Pot Size	Specification	Density	Qty.
Cala_acu 'KS'	Calamagrostis x acutiflora 'Karl Foerster'	3L	Full Pot; C	4/m²	14 No.
Care_pen	Carex pendula	3L	Full Pot; C	3/m²	31 No.
Desc_ces 'G'	Deschampsia cespitosa 'Goldschleier'	3L	Full Pot; C	3/m²	86 No.
Penn_alo 'H'	Pennisetum alopecuroides 'Hamelin'	3L	Full Pot; C	3/m²	67 No.

Climbers

Abbreviation	Species	Height	Pot Size	Specification	Density	Qty.
Ceap_thyr	Ceanothus thyrsiflorus repens		5L	Bushy; 5 brks; C	Counted	9 No.
Clem_mon 'E'	Clematis montana 'Elizabeth'	80-100cm	5L	Trained to wall with wires; Several Shoots; 2 brks; C	Counted	5 No.
Esca_mac	Escallonia rubra macrantha	60-80cm	5L	Bushy; 5 brks; C	Counted	3 No.
Euon_fort 'SQ'	Euonymus fortunei 'Silver Queen'	20-30cm	5L	Bushy; 7 brks; C	Counted	24 No.
Garr_elli 'JR'	Garrya elliptica 'James Roof'	80-100cm	10L	Leader with Laterals; 5 brks; C	Counted	3 No.
Hed_hel	Hedera helix	80-100cm	5L	Cared; Several Shoots; 2 brks; C	Counted	13 No.
Hydra_peti	Hydrangea anomala petiolaris	80-100cm	5L	Cared; Several Shoots; 4 brks; C	Counted	24 No.
Hydra_peti	Hydrangea anomala petiolaris	80-100cm	5L	Cared; Several Shoots; 4 brks; C	3/m²	5 No.
Ilex_aqui 'JCVT'	Ilex aquifolium 'J.C. van Tol'	80-100cm	10L	Cared; Leader with Laterals; C	Counted	1 No.
Jas_offi	Jasminum officinale	80-100cm	5L	Trained to wall with wires; Several Shoots; 2 brks; C	Counted	4 No.
Pass_caer	Passiflora caerulea	80-100cm	5L	Trained to wall with wires; Several Shoots; 2 brks; C	Counted	4 No.
Rosa_'FEL'	Rosa 'Francis E Lester'	80-100cm	5L	Trained to wall with wires; Several Shoots; 2 brks; C	Counted	11 No.
Trac_jas	Trachelospermum jasminoides	80-100cm	10L	With frame/ wires; Several Shoots; 2 brks; C	Counted	3 No.
Vitis_coig	Vitis coignetiae	80-100cm	5L	Trained to wall with wires; Several Shoots; 2 brks; C	Counted	10 No.

0m 5m 10m

north

- All dimensions in millimetres unless otherwise indicated. All levels in metres relative to Ordnance Datum and are positive (AOD) unless otherwise indicated.
- Figured dimensions only to be taken from this drawing, do not scale except for planning purposes. All dimensions to be checked on site.
- For civil and structural matters including existing and proposed services, sub-base construction and site structures (including retaining walls over 900mm height) refer to information by others.
- The original version of this drawing was produced in colour - monochrome copies should not be relied upon to accurately reflect all drawing elements.
- This drawing has been prepared for tender purposes only and should not be used for construction.

Site boundary
Topographical survey information - dwg. PLN-6000 by Cadmap dated March 2021
Existing trees to be retained and protected in accordance with BS 5837:2012 - refer to arboricultural report 10948 TCP 01 by Aspect Arboriculture dated June 2021
Root Protection Area - refer to arboricultural report. To remain undisturbed and uncompacted (no material or equipment storage permitted)
Existing tree to be removed
Proposed building
Cobble rumble strip
Emergency access route
Bitmac surface to primary road
Bitmac surface to secondary road
Bitmac pavement
Block paved shared surface - colour (brindle / buff) to tie in with brick colour of buildings in character areas
Block paving to driveways - colour (brindle / buff) to tie in with brick colour of buildings in character areas
Block paving to private patios
Fittleworth stone footpath
Bark mulch path (to maintenance paths)
Large street tree
Smaller street tree
Native buffer trees
Tree to central Public Open Space
Sensory trees to LEAP
Ornamental tree at entrance
Shrubs (including native and ornamental)
Sensory planting to play area
Amenity grass to rear gardens
Wildflower grass to public open space
Grassland mix
Native hedge buffer planting, to site boundaries with post and wire
Native hedge (internal) with post and wire
Close board fence to rear gardens
Combined boundary wall and fence (to key outer faces)
Post and rail fence with stock proof mesh
Low fence to ground floor apartment patios
Proposed play equipment
Earth mound play feature
Rubber crumb safety surface
Metal gate to play area
Telescopic bollards to emergency access route
Knee rail to POS
Wooden steps to bridleway
Climbers



rev	date	by	chk	notes
P03	03.12.24	MS	EB	Updated to latest layout
P02	04.08.23	EB	LF	Issue for tender
P01	28.07.23	EB	LF	Draft issue for comment

project Land South of Crawley Down Road, Felbridge

title Planting plan - ornamental (1 of 16)

status Tender **scale @ A0** 1:200

dwg no PLN-1-5005

references 220620 Site Plan (1101 Rev.I) by Boyer Planning
10948 TCP 01 by aspect arboriculture
PLN-6000 by Cadmap

terrafirma
LANDSCAPE ARCHITECTS
Suite B, Ideal House, Bedford Road, Petersfield, Hampshire GU32 3QA
Tel. +44 (0)1730 262 040
Web. www.terrafirmaprojects.com
© Copyright reserved 2024