

This drawing is confidential & the copyright of N Smith Electrical Ltd, the contents are not to be used or copied for any purpose whatsoever without our prior written consent. Do not scale off this drawing. All dimensions in millimeters except where otherwise stated

Interior designers special luminaires

- SP1 Special Light fitting as per interior designers spec Provisional Sum £100.00 each
- SP2 Special Light fitting as per interior designers spec Provisional Sum £100.00 each
- SP3 Special Light fitting as per interior designers spec Provisional Sum £150.00 each
- SP4 Special Light fitting as per interior designers spec Provisional Sum £250.00 each
- Track 1 3Mts long lighting track with 3No luminaires as per interior designers spec Provisional Sum £500.00 per track
- Track 2 3Mts long lighting track with 3No luminaires as per interior designers spec Provisional Sum £500.00 per track
- Track 3 3Mts long lighting track with 3No luminaires as per interior designers spec Provisional Sum £500.00 per track
- Track 4 6Mts long lighting track with 5No luminaires as per interior designers spec Provisional Sum £1000.00 per track

- 1 way Light Switch
- 2 way Light Switch
- Retractive Switch
- Key Operated Light Switch
- Intermediate Light Switch
- Fan Isolator Switch
- Stand alone flush/surface ceiling mounted presence detector
- Stand alone flush/surface ceiling mounted absence detector
- Corridor dimming function flush ceiling mounted presence detector
- Daylight Sensor
- Lighting scene set controller plate
- Photo cell control unit

- AE NVC Lighting Cleveland NCV1X5M3L840 LED Corrosion resistant linear batten 35W 3935 Lumens 4000K 1500mm CW 3hr emergency pack
- BE NVC Lighting Preston NPE21M3L830-840 Surface circular LED bulkhead 19W 2083 Lumens 4000K CW 3hr emergency pack
- B1 NVC Lighting Preston NPE21MMW30-840 Surface circular LED bulkhead 19W 2083 Lumens 4000K CW 3hr emergency pack
- B1E NVC Lighting Preston NPE21MMW3L830-840 Surface circular LED bulkhead with Microwave sensor 19W 2083 Lumens 4000K CW 3hr emergency pack
- C NVC Lighting Washington NWA6-18/840 Recessed LED down light set to 19W 2643 Lumens
- CE NVC Lighting Washington NWA6-18/840 Recessed LED down light set to 19W 2643 Lumens plus NRECM3PACKV2 emergency pack
- D NVC Lighting Bismarck NB28/840TPA IP54 600x600 Lay-in LED panel 28W 3435 Lumens 4000K
- DE NVC Lighting Bismarck NB28/840TPA IP54 600x600 Lay-in LED panel 28W 3435 Lumens 4000K c/w NRECM3PACKV2 emergency pack
- E01 NVC Lighting Seneca LFE NSC/SURF-W/DANM3 surface mounted non maintained emergency down light wide a wide lens 1.3W 200 Lumens
- F NVC Lighting Brooklyn NBR18-28/830-40-60 Wall mounted external LED bulkhead set to 28W 2958 Lumens 3000K
- FE NVC Lighting Brooklyn NBR18-28M3L830-40-60 Wall mounted external LED bulkhead set to 28W 2958 Lumens 3000K CW 3hr emergency pack
- LT NVC Lighting Arlington NALM3/ISO-U Illuminated exit sign, suspended, wall mounted, recessed.
- LT NVC Lighting Greenland Pro NGN652-74/D/840 Corrosion resistant LED batten Dali Dimming set to 61W 9937 Lumens 4000K
- Easlumine Asola LN13-2-2953-840-D Suspended Continuous lighting profile Dali LED with opal diffuser, 48W 6241 Lumens 4000K 2953mm long
- Easlumine Asola LN13-2-2953-840-D-E Suspended Continuous lighting profile Dali LED with opal diffuser, 48W 6241 Lumens 4000K 2953mm long c/w emergency



T3	Revised Tender Issue following review	10.06.26
T2	Revised Tender Issue	02.06.26
T1	Tender Issue	13.05.26
P2	Continuous lighting updated	08.06.26
P1	Issued for Stage 3 design & Comments	27.02.26

Rev	Description	Date
-----	-------------	------

Client	Hurstpierpoint College
--------	------------------------

N SMITH

Project

Phase 2, Sports Hub

Title

Electrical Services
FF Lighting Installation

Scale	1:75 @ A1	
Drawn	BWL	Checked RJ
Job No	J5662	Rev T3