



THE CONTRACTOR IS TO ASCERTAIN THE EXACT POSITION/DEPTH OF ALL SERVICES, INCLUDING BUT NOT LIMITED TO:

- SURFACE WATER & FOUL DRAINAGE
- WATER
- ELECTRICITY
- TELECOMMUNICATIONS
- CCTV
- GAS
- ANY OTHER UTILITIES WHICH MAY BE PRESENT

ALL TEMPORARY WORKS ARE THE RESPONSIBILITY OF THE CONTRACTOR. ALL TEMPORARY WORKS ARE TO BE DESIGNED & DETAILED BY THE CONTRACTOR. SHORING/PROPPING ARRANGEMENTS ARE TO BE ADEQUATE TO SUPPORT ALL APPLIED LOADS AND CONSIDERATION GIVEN TO THE ADJACENT STRUCTURE IN THE TEMPORARY CONDITION

-  80mm dia Perforated Lateral Drain
 100mm dia Perforated Lateral Drain
 150mm dia Solid Twin Wall Carrier Drain
 150mm dia Perforated Cut Off Drain
 225mm dia Solid Twin Walled Carrier Drain
-  1.2m dia Concrete Chamber
 1.2m dia Concrete Chamber With Silt Trap
 900mm X 600mm Chamber

*ISSUED FOR
CONSTRUCTION.*

REV	DATE	DESCRIPTION	BY	CHKD
	27 05 26	OUTLET NOTE ADDED	JS	JS

ENT
MCARDLE SPORT TEC

PROJECT IMBERHORNE FARM NATURAL TURF SPORTS FACILITY DEVELOPMENT LE DRAINAGE SYSTEM LAYOUT

DATE	23 March 2026	PRODUCED BY	JNGS
SCALE	1:500	CHECKED	
D REF		APPROVED	

ORIGINAL DRAWING SIZE A1



EO Turf Consulting Limited
2 Cog Road
Llully
Llanale of Glamorgan
F64 5TE
Tel : 029 2053 1335
Fax : 05600 432179
Email : enquiries@geoturfconsulting.com

Job No.	DRAWING No.	REV.
TC001046 SK02		A