

|                                                              |                                                                    |                                                                                     |
|--------------------------------------------------------------|--------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| RSK LDE                                                      |                                                                    | Page 1                                                                              |
| 18 Frogmore Road<br>Hemel Hempstead<br>Hertfordshire HP3 9RT | West Hoathly Brickworks<br>Sharpthorne<br>Network 1 SW Calculation |  |
| Date 20/07/2023 16:56<br>File 134285_ SW NETWORK 1_RE...     | Designed by AMuthusami<br>Checked by                               |                                                                                     |
| XP Solutions                                                 | Network 2020.1.3                                                   |                                                                                     |

### STORM SEWER DESIGN by the Modified Rational Method

#### Design Criteria for Surface Network 3

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

|                                      |        |                                       |       |
|--------------------------------------|--------|---------------------------------------|-------|
| Return Period (years)                | 100    | PIMP (%)                              | 100   |
| M5-60 (mm)                           | 20.000 | Add Flow / Climate Change (%)         | 45    |
| Ratio R                              | 0.400  | Minimum Backdrop Height (m)           | 0.200 |
| Maximum Rainfall (mm/hr)             | 50     | Maximum Backdrop Height (m)           | 1.500 |
| Maximum Time of Concentration (mins) | 30     | Min Design Depth for Optimisation (m) | 1.200 |
| Foul Sewage (l/s/ha)                 | 0.000  | Min Vel for Auto Design only (m/s)    | 1.00  |
| Volumetric Runoff Coeff.             | 0.750  | Min Slope for Optimisation (1:X)      | 500   |

Designed with Level Soffits

#### Time Area Diagram for Surface Network 3

| Time<br>(mins) | Area<br>(ha) | Time<br>(mins) | Area<br>(ha) |
|----------------|--------------|----------------|--------------|
| 0-4            | 0.588        | 4-8            | 2.093        |

Total Area Contributing (ha) = 2.681

Total Pipe Volume (m³) = 18.859

#### Network Design Table for Surface Network 3

« - Indicates pipe capacity < flow

| PN    | Length<br>(m) | Fall<br>(m) | Slope<br>(1:X) | I.Area<br>(ha) | T.E.<br>(mins) | Base<br>Flow (l/s) | k<br>(mm) | HYD<br>SECT | DIA<br>(mm) | Section Type | Auto<br>Design                                                                        |
|-------|---------------|-------------|----------------|----------------|----------------|--------------------|-----------|-------------|-------------|--------------|---------------------------------------------------------------------------------------|
| 1.000 | 21.976        | 0.120       | 183.1          | 2.609          | 5.00           | 0.0                | 0.600     | o           | 150         | Pipe/Conduit |  |
| 1.001 | 15.806        | 0.450       | 35.1           | 0.000          | 0.00           | 0.0                | 0.600     | o           | 300         | Pipe/Conduit |  |
| 1.002 | 31.958        | 0.730       | 43.8           | 0.000          | 0.00           | 0.0                | 0.600     | o           | 300         | Pipe/Conduit |  |
| 1.003 | 33.324        | 0.470       | 70.9           | 0.000          | 0.00           | 0.0                | 0.600     | o           | 300         | Pipe/Conduit |  |
| 1.004 | 14.198        | 0.120       | 118.3          | 0.000          | 0.00           | 0.0                | 0.600     | o           | 300         | Pipe/Conduit |  |

#### Network Results Table

| PN    | Rain<br>(mm/hr) | T.C.<br>(mins) | US/IL<br>(m) | Σ I.Area<br>(ha) | Σ Base<br>Flow (l/s) | Foul<br>(l/s) | Add Flow<br>(l/s) | Vel<br>(m/s) | Cap<br>(l/s) | Flow<br>(l/s) |
|-------|-----------------|----------------|--------------|------------------|----------------------|---------------|-------------------|--------------|--------------|---------------|
| 1.000 | 50.00           | 5.50           | 117.120      | 2.609            | 0.0                  | 0.0           | 159.0             | 0.74         | 13.1«        | 512.3         |
| 1.001 | 50.00           | 5.59           | 117.000      | 2.609            | 0.0                  | 0.0           | 159.0             | 2.66         | 188.1«       | 512.3         |
| 1.002 | 50.00           | 5.82           | 116.550      | 2.609            | 0.0                  | 0.0           | 159.0             | 2.38         | 168.4«       | 512.3         |
| 1.003 | 50.00           | 6.11           | 115.820      | 2.609            | 0.0                  | 0.0           | 159.0             | 1.87         | 132.2«       | 512.3         |
| 1.004 | 50.00           | 6.28           | 115.350      | 2.609            | 0.0                  | 0.0           | 159.0             | 1.44         | 102.1«       | 512.3         |

|                                                              |                                                                    |                                                                                     |
|--------------------------------------------------------------|--------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| RSK LDE                                                      |                                                                    | Page 2                                                                              |
| 18 Frogmore Road<br>Hemel Hempstead<br>Hertfordshire HP3 9RT | West Hoathly Brickworks<br>Sharpthorne<br>Network 1 SW Calculation |  |
| Date 20/07/2023 16:56<br>File 134285_ SW NETWORK 1_RE...     | Designed by AMuthusami<br>Checked by                               |                                                                                     |
| XP Solutions                                                 | Network 2020.1.3                                                   |                                                                                     |

#### Network Design Table for Surface Network 3

| PN    | Length<br>(m) | Fall<br>(m) | Slope<br>(1:X) | I.Area<br>(ha) | T.E.<br>(mins) | Base<br>Flow (l/s) | k<br>(mm) | HYD<br>SECT | DIA<br>(mm) | Section Type | Auto<br>Design                                                                        |
|-------|---------------|-------------|----------------|----------------|----------------|--------------------|-----------|-------------|-------------|--------------|---------------------------------------------------------------------------------------|
| 1.005 | 23.948        | 0.095       | 252.1          | 0.000          | 0.00           | 0.0                | 0.600     | o           | 300         | Pipe/Conduit |    |
| 1.006 | 28.701        | 0.115       | 249.6          | 0.000          | 0.00           | 0.0                | 0.600     | o           | 300         | Pipe/Conduit |    |
| 1.007 | 11.270        | 0.190       | 59.3           | 0.000          | 0.00           | 0.0                | 0.600     | o           | 300         | Pipe/Conduit |    |
| 1.008 | 14.698        | 0.120       | 122.5          | 0.000          | 0.00           | 0.0                | 0.600     | o           | 300         | Pipe/Conduit |    |
| 1.009 | 19.010        | 0.140       | 135.8          | 0.000          | 0.00           | 0.0                | 0.600     | o           | 300         | Pipe/Conduit |    |
| 1.010 | 10.363        | 0.118       | 87.8           | 0.000          | 0.00           | 0.0                | 0.600     | o           | 300         | Pipe/Conduit |    |
| 2.000 | 15.904        | 0.050       | 318.1          | 0.018          | 5.00           | 0.0                | 0.600     | o           | 150         | Pipe/Conduit |    |
| 2.001 | 18.304        | 0.050       | 366.1          | 0.018          | 0.00           | 0.0                | 0.600     | o           | 150         | Pipe/Conduit |    |
| 2.002 | 14.927        | 0.050       | 298.5          | 0.018          | 0.00           | 0.0                | 0.600     | o           | 150         | Pipe/Conduit |    |
| 2.003 | 15.346        | 0.050       | 306.9          | 0.018          | 0.00           | 0.0                | 0.600     | o           | 150         | Pipe/Conduit |    |
| 2.004 | 11.279        | 0.150       | 75.2           | 0.000          | 0.00           | 0.0                | 0.600     | o           | 150         | Pipe/Conduit |    |
| 2.005 | 64.811        | 4.123       | 15.7           | 0.000          | 0.00           | 0.0                | 0.600     | o           | 150         | Pipe/Conduit |    |
| 1.011 | 22.892        | 0.452       | 50.6           | 0.000          | 0.00           | 0.0                | 0.600     | o           | 300         | Pipe/Conduit |  |

#### Network Results Table

| PN    | Rain<br>(mm/hr) | T.C.<br>(mins) | US/IL<br>(m) | Σ I.Area<br>(ha) | Σ Base<br>Flow (l/s) | Foul<br>(l/s) | Add Flow<br>(l/s) | Vel<br>(m/s) | Cap<br>(l/s) | Flow<br>(l/s) |
|-------|-----------------|----------------|--------------|------------------|----------------------|---------------|-------------------|--------------|--------------|---------------|
| 1.005 | 50.00           | 6.68           | 115.230      | 2.609            | 0.0                  | 0.0           | 159.0             | 0.99         | 69.7<        | 512.3         |
| 1.006 | 50.00           | 7.17           | 115.135      | 2.609            | 0.0                  | 0.0           | 159.0             | 0.99         | 70.0<        | 512.3         |
| 1.007 | 50.00           | 7.26           | 115.020      | 2.609            | 0.0                  | 0.0           | 159.0             | 2.05         | 144.6<       | 512.3         |
| 1.008 | 50.00           | 7.43           | 114.830      | 2.609            | 0.0                  | 0.0           | 159.0             | 1.42         | 100.3<       | 512.3         |
| 1.009 | 50.00           | 7.67           | 114.710      | 2.609            | 0.0                  | 0.0           | 159.0             | 1.35         | 95.2<        | 512.3         |
| 1.010 | 50.00           | 7.77           | 114.570      | 2.609            | 0.0                  | 0.0           | 159.0             | 1.68         | 118.7<       | 512.3         |
| 2.000 | 50.00           | 5.47           | 119.000      | 0.018            | 0.0                  | 0.0           | 1.1               | 0.56         | 9.9          | 3.5           |
| 2.001 | 50.00           | 6.06           | 118.950      | 0.036            | 0.0                  | 0.0           | 2.2               | 0.52         | 9.2          | 7.1           |
| 2.002 | 50.00           | 6.49           | 118.900      | 0.054            | 0.0                  | 0.0           | 3.3               | 0.58         | 10.2<        | 10.6          |
| 2.003 | 50.00           | 6.94           | 118.850      | 0.072            | 0.0                  | 0.0           | 4.4               | 0.57         | 10.0<        | 14.1          |
| 2.004 | 50.00           | 7.11           | 118.800      | 0.072            | 0.0                  | 0.0           | 4.4               | 1.16         | 20.5         | 14.1          |
| 2.005 | 50.00           | 7.53           | 118.650      | 0.072            | 0.0                  | 0.0           | 4.4               | 2.55         | 45.1         | 14.1          |
| 1.011 | 50.00           | 7.94           | 114.452      | 2.681            | 0.0                  | 0.0           | 163.4             | 2.21         | 156.5<       | 526.4         |

|                                                              |                                                                    |                                                                                     |
|--------------------------------------------------------------|--------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| RSK LDE                                                      |                                                                    | Page 3                                                                              |
| 18 Frogmore Road<br>Hemel Hempstead<br>Hertfordshire HP3 9RT | West Hoathly Brickworks<br>Sharpthorne<br>Network 1 SW Calculation |  |
| Date 20/07/2023 16:56<br>File 134285_ SW NETWORK 1_RE...     | Designed by AMuthusami<br>Checked by                               |                                                                                     |
| XP Solutions                                                 | Network 2020.1.3                                                   |                                                                                     |

Manhole Schedules for Surface Network 3

| MH Name | MH CL (m) | MH Depth (m) | MH Connection | MH Diam., L*W (mm) | PN    | Pipe Out Invert Level (m) | Pipe Out Diameter (mm) | PN    | Pipes In Invert Level (m) | Pipes In Diameter (mm) | Backdrop (mm) |
|---------|-----------|--------------|---------------|--------------------|-------|---------------------------|------------------------|-------|---------------------------|------------------------|---------------|
| S62     | 118.520   | 1.400        | Open Manhole  | 1350               | 1.000 | 117.120                   | 150                    |       |                           |                        |               |
| S77     | 118.520   | 1.520        | Open Manhole  | 1350               | 1.001 | 117.000                   | 300                    | 1.000 | 117.000                   | 150                    |               |
| S1      | 120.280   | 3.730        | Open Manhole  | 1200               | 1.002 | 116.550                   | 300                    | 1.001 | 116.550                   | 300                    |               |
| S2      | 119.125   | 3.305        | Open Manhole  | 1200               | 1.003 | 115.820                   | 300                    | 1.002 | 115.820                   | 300                    |               |
| S3      | 117.750   | 2.400        | Open Manhole  | 1200               | 1.004 | 115.350                   | 300                    | 1.003 | 115.350                   | 300                    |               |
| S5      | 117.327   | 2.097        | Open Manhole  | 1200               | 1.005 | 115.230                   | 300                    | 1.004 | 115.230                   | 300                    |               |
| S6      | 117.647   | 2.512        | Open Manhole  | 1200               | 1.006 | 115.135                   | 300                    | 1.005 | 115.135                   | 300                    |               |
| S7      | 117.900   | 2.880        | Open Manhole  | 1200               | 1.007 | 115.020                   | 300                    | 1.006 | 115.020                   | 300                    |               |
| S8      | 117.866   | 3.036        | Open Manhole  | 1350               | 1.008 | 114.830                   | 300                    | 1.007 | 114.830                   | 300                    |               |
| S9      | 117.694   | 2.984        | Open Manhole  | 1200               | 1.009 | 114.710                   | 300                    | 1.008 | 114.710                   | 300                    |               |
| S10     | 117.239   | 2.669        | Open Manhole  | 1200               | 1.010 | 114.570                   | 300                    | 1.009 | 114.570                   | 300                    |               |
| S63     | 119.300   | 0.300        | Open Manhole  | 1350               | 2.000 | 119.000                   | 150                    |       |                           |                        |               |
| S64     | 119.250   | 0.300        | Open Manhole  | 1350               | 2.001 | 118.950                   | 150                    | 2.000 | 118.950                   | 150                    |               |
| S65     | 119.200   | 0.300        | Open Manhole  | 1350               | 2.002 | 118.900                   | 150                    | 2.001 | 118.900                   | 150                    |               |
| S66     | 119.150   | 0.300        | Open Manhole  | 1350               | 2.003 | 118.850                   | 150                    | 2.002 | 118.850                   | 150                    |               |
| S67     | 119.100   | 0.300        | Open Manhole  | 1350               | 2.004 | 118.800                   | 150                    | 2.003 | 118.800                   | 150                    |               |
| S68     | 120.822   | 2.172        | Open Manhole  | 1200               | 2.005 | 118.650                   | 150                    | 2.004 | 118.650                   | 150                    |               |
| S11     | 115.756   | 1.304        | Open Manhole  | 1350               | 1.011 | 114.452                   | 300                    | 1.010 | 114.452                   | 300                    |               |
|         |           |              |               |                    |       |                           |                        | 2.005 | 114.527                   | 150                    |               |
| S12     | 115.425   | 1.425        | Open Manhole  | 0                  |       | OUTFALL                   |                        | 1.011 | 114.000                   | 300                    |               |

| MH Name | Manhole Easting (m) | Manhole Northing (m) | Intersection Easting (m) | Intersection Northing (m) | Manhole Access | Layout (North)                                                                        |
|---------|---------------------|----------------------|--------------------------|---------------------------|----------------|---------------------------------------------------------------------------------------|
| S62     | 537361.640          | 132889.389           | 537361.640               | 132889.389                | Required       |  |
| S77     | 537349.379          | 132907.627           | 537349.379               | 132907.627                | Required       |  |
| S1      | 537345.322          | 132922.903           | 537345.322               | 132922.903                | Required       |  |
| S2      | 537351.496          | 132954.259           | 537351.496               | 132954.259                | Required       |  |
| S3      | 537320.572          | 132966.676           | 537320.572               | 132966.676                | Required       |  |



|                                                              |                                                                    |
|--------------------------------------------------------------|--------------------------------------------------------------------|
| RSK LDE                                                      | Page 5                                                             |
| 18 Frogmore Road<br>Hemel Hempstead<br>Hertfordshire HP3 9RT | West Hoathly Brickworks<br>Sharpthorne<br>Network 1 SW Calculation |
| Date 20/07/2023 16:56<br>File 134285_ SW NETWORK 1_RE...     | Designed by AMuthusami<br>Checked by                               |
| XP Solutions                                                 | Network 2020.1.3                                                   |



### PIPELINE SCHEDULES for Surface Network 3

#### Upstream Manhole

| PN    | Hyd Sect | Diam (mm) | MH Name | C.Level (m) | I.Level (m) | D.Depth (m) | MH Connection | MH DIAM., L*W (mm) |
|-------|----------|-----------|---------|-------------|-------------|-------------|---------------|--------------------|
| 1.000 | o        | 150       | S62     | 118.520     | 117.120     | 1.250       | Open Manhole  | 1350               |
| 1.001 | o        | 300       | S77     | 118.520     | 117.000     | 1.220       | Open Manhole  | 1350               |
| 1.002 | o        | 300       | S1      | 120.280     | 116.550     | 3.430       | Open Manhole  | 1200               |
| 1.003 | o        | 300       | S2      | 119.125     | 115.820     | 3.005       | Open Manhole  | 1200               |
| 1.004 | o        | 300       | S3      | 117.750     | 115.350     | 2.100       | Open Manhole  | 1200               |
| 1.005 | o        | 300       | S5      | 117.327     | 115.230     | 1.797       | Open Manhole  | 1200               |
| 1.006 | o        | 300       | S6      | 117.647     | 115.135     | 2.212       | Open Manhole  | 1200               |
| 1.007 | o        | 300       | S7      | 117.900     | 115.020     | 2.580       | Open Manhole  | 1200               |
| 1.008 | o        | 300       | S8      | 117.866     | 114.830     | 2.736       | Open Manhole  | 1350               |
| 1.009 | o        | 300       | S9      | 117.694     | 114.710     | 2.684       | Open Manhole  | 1200               |
| 1.010 | o        | 300       | S10     | 117.239     | 114.570     | 2.369       | Open Manhole  | 1200               |
| 2.000 | o        | 150       | S63     | 119.300     | 119.000     | 0.150       | Open Manhole  | 1350               |
| 2.001 | o        | 150       | S64     | 119.250     | 118.950     | 0.150       | Open Manhole  | 1350               |
| 2.002 | o        | 150       | S65     | 119.200     | 118.900     | 0.150       | Open Manhole  | 1350               |
| 2.003 | o        | 150       | S66     | 119.150     | 118.850     | 0.150       | Open Manhole  | 1350               |
| 2.004 | o        | 150       | S67     | 119.100     | 118.800     | 0.150       | Open Manhole  | 1350               |
| 2.005 | o        | 150       | S68     | 120.822     | 118.650     | 2.022       | Open Manhole  | 1200               |
| 1.011 | o        | 300       | S11     | 115.756     | 114.452     | 1.004       | Open Manhole  | 1350               |

#### Downstream Manhole

| PN    | Length (m) | Slope (1:X) | MH Name | C.Level (m) | I.Level (m) | D.Depth (m) | MH Connection | MH DIAM., L*W (mm) |
|-------|------------|-------------|---------|-------------|-------------|-------------|---------------|--------------------|
| 1.000 | 21.976     | 183.1       | S77     | 118.520     | 117.000     | 1.370       | Open Manhole  | 1350               |
| 1.001 | 15.806     | 35.1        | S1      | 120.280     | 116.550     | 3.430       | Open Manhole  | 1200               |
| 1.002 | 31.958     | 43.8        | S2      | 119.125     | 115.820     | 3.005       | Open Manhole  | 1200               |
| 1.003 | 33.324     | 70.9        | S3      | 117.750     | 115.350     | 2.100       | Open Manhole  | 1200               |
| 1.004 | 14.198     | 118.3       | S5      | 117.327     | 115.230     | 1.797       | Open Manhole  | 1200               |
| 1.005 | 23.948     | 252.1       | S6      | 117.647     | 115.135     | 2.212       | Open Manhole  | 1200               |
| 1.006 | 28.701     | 249.6       | S7      | 117.900     | 115.020     | 2.580       | Open Manhole  | 1200               |
| 1.007 | 11.270     | 59.3        | S8      | 117.866     | 114.830     | 2.736       | Open Manhole  | 1350               |
| 1.008 | 14.698     | 122.5       | S9      | 117.694     | 114.710     | 2.684       | Open Manhole  | 1200               |
| 1.009 | 19.010     | 135.8       | S10     | 117.239     | 114.570     | 2.369       | Open Manhole  | 1200               |
| 1.010 | 10.363     | 87.8        | S11     | 115.756     | 114.452     | 1.004       | Open Manhole  | 1350               |
| 2.000 | 15.904     | 318.1       | S64     | 119.250     | 118.950     | 0.150       | Open Manhole  | 1350               |
| 2.001 | 18.304     | 366.1       | S65     | 119.200     | 118.900     | 0.150       | Open Manhole  | 1350               |
| 2.002 | 14.927     | 298.5       | S66     | 119.150     | 118.850     | 0.150       | Open Manhole  | 1350               |
| 2.003 | 15.346     | 306.9       | S67     | 119.100     | 118.800     | 0.150       | Open Manhole  | 1350               |
| 2.004 | 11.279     | 75.2        | S68     | 120.822     | 118.650     | 2.022       | Open Manhole  | 1200               |
| 2.005 | 64.811     | 15.7        | S11     | 115.756     | 114.527     | 1.079       | Open Manhole  | 1350               |
| 1.011 | 22.892     | 50.6        | S12     | 115.425     | 114.000     | 1.125       | Open Manhole  | 0                  |



|                                                              |                                                                    |                                                                                     |
|--------------------------------------------------------------|--------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| RSK LDE                                                      |                                                                    | Page 7                                                                              |
| 18 Frogmore Road<br>Hemel Hempstead<br>Hertfordshire HP3 9RT | West Hoathly Brickworks<br>Sharpthorne<br>Network 1 SW Calculation |  |
| Date 20/07/2023 16:56<br>File 134285_ SW NETWORK 1_RE...     | Designed by AMuthusami<br>Checked by                               |                                                                                     |
| XP Solutions                                                 | Network 2020.1.3                                                   |                                                                                     |

### Storage Structures for Surface Network 3

#### Tank or Pond Manhole: S62, DS/PN: 1.000

Invert Level (m) 117.120

| Depth (m) | Area (m <sup>2</sup> ) | Depth (m) | Area (m <sup>2</sup> ) | Depth (m) | Area (m <sup>2</sup> ) | Depth (m) | Area (m <sup>2</sup> ) |
|-----------|------------------------|-----------|------------------------|-----------|------------------------|-----------|------------------------|
| 0.000     | 13435.0                | 0.400     | 17760.0                | 0.800     | 22281.0                | 1.200     | 22281.0                |
| 0.100     | 15061.0                | 0.500     | 18696.0                | 0.900     | 22281.0                | 1.300     | 22281.0                |
| 0.200     | 15849.0                | 0.600     | 20435.0                | 1.000     | 22281.0                | 1.400     | 22281.0                |
| 0.300     | 16796.0                | 0.700     | 22281.0                | 1.100     | 22281.0                |           |                        |

#### Swale Manhole: S63, DS/PN: 2.000

Warning:- Volume should always be included unless the upstream pipe is being used for storage and/or as a carrier

|                                      |         |                            |       |
|--------------------------------------|---------|----------------------------|-------|
| Infiltration Coefficient Base (m/hr) | 0.00000 | Length (m)                 | 16.7  |
| Infiltration Coefficient Side (m/hr) | 0.00000 | Side Slope (1:X)           | 3.0   |
| Safety Factor                        | 2.0     | Slope (1:X)                | 334.0 |
| Porosity                             | 1.00    | Cap Volume Depth (m)       | 0.000 |
| Invert Level (m)                     | 119.000 | Cap Infiltration Depth (m) | 0.000 |
| Base Width (m)                       | 1.0     | Include Swale Volume       | Yes   |

#### Swale Manhole: S64, DS/PN: 2.001

Warning:- Volume should always be included unless the upstream pipe is being used for storage and/or as a carrier

|                                      |         |                            |       |
|--------------------------------------|---------|----------------------------|-------|
| Infiltration Coefficient Base (m/hr) | 0.00000 | Length (m)                 | 17.7  |
| Infiltration Coefficient Side (m/hr) | 0.00000 | Side Slope (1:X)           | 3.0   |
| Safety Factor                        | 2.0     | Slope (1:X)                | 355.0 |
| Porosity                             | 1.00    | Cap Volume Depth (m)       | 0.000 |
| Invert Level (m)                     | 118.950 | Cap Infiltration Depth (m) | 0.000 |
| Base Width (m)                       | 1.0     | Include Swale Volume       | Yes   |

#### Swale Manhole: S65, DS/PN: 2.002

Warning:- Volume should always be included unless the upstream pipe is being used for storage and/or as a carrier

|                                      |         |                            |       |
|--------------------------------------|---------|----------------------------|-------|
| Infiltration Coefficient Base (m/hr) | 0.00000 | Length (m)                 | 15.2  |
| Infiltration Coefficient Side (m/hr) | 0.00000 | Side Slope (1:X)           | 3.0   |
| Safety Factor                        | 2.0     | Slope (1:X)                | 304.0 |
| Porosity                             | 1.00    | Cap Volume Depth (m)       | 0.000 |
| Invert Level (m)                     | 118.900 | Cap Infiltration Depth (m) | 0.000 |
| Base Width (m)                       | 1.0     | Include Swale Volume       | Yes   |

|                                                              |                                                                    |                                                                                     |
|--------------------------------------------------------------|--------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| RSK LDE                                                      |                                                                    | Page 8                                                                              |
| 18 Frogmore Road<br>Hemel Hempstead<br>Hertfordshire HP3 9RT | West Hoathly Brickworks<br>Sharpthorne<br>Network 1 SW Calculation |  |
| Date 20/07/2023 16:56<br>File 134285_ SW NETWORK 1_RE...     | Designed by AMuthusami<br>Checked by                               |                                                                                     |
| XP Solutions Network 2020.1.3                                |                                                                    |                                                                                     |

Swale Manhole: S66, DS/PN: 2.003

Warning:- Volume should always be included unless the upstream pipe is being used for storage and/or as a carrier

|                                      |         |                            |       |
|--------------------------------------|---------|----------------------------|-------|
| Infiltration Coefficient Base (m/hr) | 0.00000 | Length (m)                 | 15.2  |
| Infiltration Coefficient Side (m/hr) | 0.00000 | Side Slope (1:X)           | 3.0   |
| Safety Factor                        | 2.0     | Slope (1:X)                | 304.0 |
| Porosity                             | 1.00    | Cap Volume Depth (m)       | 0.000 |
| Invert Level (m)                     | 118.900 | Cap Infiltration Depth (m) | 0.000 |
| Base Width (m)                       | 1.0     | Include Swale Volume       | Yes   |

©1982-2020 Innovyze



|                                                              |                                                                    |                                                                                     |
|--------------------------------------------------------------|--------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| RSK LDE                                                      |                                                                    | Page 10                                                                             |
| 18 Frogmore Road<br>Hemel Hempstead<br>Hertfordshire HP3 9RT | West Hoathly Brickworks<br>Sharpthorne<br>Network 1 SW Calculation |  |
| Date 20/07/2023 16:56<br>File 134285_ SW NETWORK 1_RE...     | Designed by AMuthusami<br>Checked by                               |                                                                                     |
| XP Solutions                                                 | Network 2020.1.3                                                   |                                                                                     |

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)  
for Surface Network 3

| PN    | US/MH<br>Name | Surcharged Flooded |                | Flow / Overflow |       | Half Drain     | Pipe          | Status     | Level<br>Exceeded |
|-------|---------------|--------------------|----------------|-----------------|-------|----------------|---------------|------------|-------------------|
|       |               | Depth<br>(m)       | Volume<br>(m³) | Cap.            | (l/s) | Time<br>(mins) | Flow<br>(l/s) |            |                   |
| 1.000 | S62           | -0.106             | 0.000          | 0.19            |       |                | 2.3           | OK         |                   |
| 1.001 | S77           | -0.279             | 0.000          | 0.01            |       |                | 2.3           | OK         |                   |
| 1.002 | S1            | -0.278             | 0.000          | 0.02            |       |                | 2.3           | OK         |                   |
| 1.003 | S2            | -0.273             | 0.000          | 0.02            |       |                | 2.3           | OK         |                   |
| 1.004 | S3            | -0.267             | 0.000          | 0.03            |       |                | 2.3           | OK         |                   |
| 1.005 | S5            | -0.263             | 0.000          | 0.04            |       |                | 2.3           | OK         |                   |
| 1.006 | S6            | -0.263             | 0.000          | 0.04            |       |                | 2.3           | OK         |                   |
| 1.007 | S7            | -0.270             | 0.000          | 0.02            |       |                | 2.3           | OK         |                   |
| 1.008 | S8            | -0.267             | 0.000          | 0.03            |       |                | 2.3           | OK         |                   |
| 1.009 | S9            | -0.267             | 0.000          | 0.03            |       |                | 2.3           | OK         |                   |
| 1.010 | S10           | -0.267             | 0.000          | 0.03            |       |                | 2.3           | OK         |                   |
| 2.000 | S63           | -0.106             | 0.000          | 0.19            |       | 7              | 1.7           | FLOOD RISK |                   |
| 2.001 | S64           | -0.094             | 0.000          | 0.30            |       | 11             | 2.6           | FLOOD RISK |                   |
| 2.002 | S65           | -0.087             | 0.000          | 0.36            |       | 13             | 3.4           | FLOOD RISK |                   |
| 2.003 | S66           | -0.077             | 0.000          | 0.48            |       | 12             | 4.4           | FLOOD RISK |                   |
| 2.004 | S67           | -0.101             | 0.000          | 0.24            |       |                | 4.4           | FLOOD RISK |                   |
| 2.005 | S68           | -0.118             | 0.000          | 0.10            |       |                | 4.4           | OK         |                   |
| 1.011 | S11           | -0.265             | 0.000          | 0.03            |       |                | 4.6           | OK         |                   |

RSK LDE

Page 11

18 Frogmore Road  
Hemel Hempstead  
Hertfordshire HP3 9RT

West Hoathly Brickworks  
Sharpthorne  
Network 1 SW Calculation

Date 20/07/2023 16:56  
File 134285\_ SW NETWORK 1\_RE...

Designed by AMuthusami  
Checked by

XP Solutions

Network 2020.1.3

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)

for Surface Network 3

Simulation Criteria

Areal Reduction Factor 1.000      Additional Flow - % of Total Flow 0.000  
Hot Start (mins) 0      MADD Factor \* 10m³/ha Storage 2.000  
Hot Start Level (mm) 0      Inlet Coefficient 0.800  
Manhole Headloss Coeff (Global) 0.500      Flow per Person per Day (l/per/day) 0.000  
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0      Number of Storage Structures 5  
Number of Online Controls 0      Number of Time/Area Diagrams 0  
Number of Offline Controls 0      Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model      FSR      Ratio R 0.400  
Region England and Wales Cv (Summer) 0.750  
M5-60 (mm)      20.000 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 450.0  
Analysis Timestep 2.5 Second Increment (Extended)  
DTS Status OFF  
DVD Status ON  
Inertia Status ON

Profile(s)      Summer and Winter  
Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440  
Return Period(s) (years) 1, 30, 100  
Climate Change (%) 0, 35, 45

Water

PN

US/MH  
Name

Storm

Return  
Period

Climate  
Change

First (X)  
Surcharge

First (Y)  
Flood

First (Z)  
Overflow

Overflow  
Act.

Level  
(m)

1.000

S62

1440 Winter

30

+35%

117.226

1.001

S77

1440 Winter

30

+35%

117.050

1.002

S1

1440 Winter

30

+35%

116.601

1.003

S2

1440 Winter

30

+35%

115.879

1.004

S3

1440 Winter

30

+35%

115.420

1.005

S5

1440 Winter

30

+35%

115.312

1.006

S6

1440 Winter

30

+35%

115.216

1.007

S7

1440 Winter

30

+35%

115.082

1.008

S8

1440 Winter

30

+35%

114.900

1.009

S9

1440 Winter

30

+35%

114.780

1.010

S10

1440 Winter

30

+35%

114.639

2.000

S63

15 Winter

30

+35%

119.091

2.001

S64

30 Winter

30

+35%

100/15 Winter

119.076

2.002

S65

30 Winter

30

+35%

100/15 Summer

119.049

2.003

S66

30 Winter

30

+35%

30/15 Winter

119.011

2.004

S67

30 Winter

30

+35%

118.883

2.005

S68

30 Winter

30

+35%

118.700

1.011

S11

60 Winter

30

+35%

114.515

©1982-2020 Innovyze

|                                                              |                                                                    |                                                                                     |
|--------------------------------------------------------------|--------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| RSK LDE                                                      |                                                                    | Page 12                                                                             |
| 18 Frogmore Road<br>Hemel Hempstead<br>Hertfordshire HP3 9RT | West Hoathly Brickworks<br>Sharpthorne<br>Network 1 SW Calculation |  |
| Date 20/07/2023 16:56<br>File 134285_ SW NETWORK 1_RE...     | Designed by AMuthusami<br>Checked by                               |                                                                                     |
| XP Solutions                                                 | Network 2020.1.3                                                   |                                                                                     |

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)  
for Surface Network 3

| PN    | US/MH<br>Name | Surcharged   | Flooded        | Flow /<br>Cap. | Overflow<br>(l/s) | Half Drain     | Pipe          | Status | Level<br>Exceeded |
|-------|---------------|--------------|----------------|----------------|-------------------|----------------|---------------|--------|-------------------|
|       |               | Depth<br>(m) | Volume<br>(m³) |                |                   | Time<br>(mins) | Flow<br>(l/s) |        |                   |
| 1.000 | S62           | -0.044       | 0.000          | 0.84           |                   |                | 10.4          |        | OK                |
| 1.001 | S77           | -0.250       | 0.000          | 0.07           |                   |                | 10.4          |        | OK                |
| 1.002 | S1            | -0.249       | 0.000          | 0.07           |                   |                | 10.4          |        | OK                |
| 1.003 | S2            | -0.241       | 0.000          | 0.09           |                   |                | 10.4          |        | OK                |
| 1.004 | S3            | -0.230       | 0.000          | 0.12           |                   |                | 10.4          |        | OK                |
| 1.005 | S5            | -0.218       | 0.000          | 0.17           |                   |                | 10.4          |        | OK                |
| 1.006 | S6            | -0.219       | 0.000          | 0.16           |                   |                | 10.4          |        | OK                |
| 1.007 | S7            | -0.238       | 0.000          | 0.10           |                   |                | 10.4          |        | OK                |
| 1.008 | S8            | -0.230       | 0.000          | 0.12           |                   |                | 10.4          |        | OK                |
| 1.009 | S9            | -0.230       | 0.000          | 0.13           |                   |                | 10.4          |        | OK                |
| 1.010 | S10           | -0.231       | 0.000          | 0.12           |                   |                | 10.4          |        | OK                |
| 2.000 | S63           | -0.059       | 0.000          | 0.56           |                   | 9              | 5.1           | FLOOD  | RISK              |
| 2.001 | S64           | -0.024       | 0.000          | 0.80           |                   | 14             | 6.9           | FLOOD  | RISK              |
| 2.002 | S65           | -0.001       | 0.000          | 0.88           |                   | 16             | 8.3           | FLOOD  | RISK              |
| 2.003 | S66           | 0.011        | 0.000          | 1.17           |                   | 17             | 10.9          | FLOOD  | RISK              |
| 2.004 | S67           | -0.067       | 0.000          | 0.59           |                   |                | 10.9          | FLOOD  | RISK              |
| 2.005 | S68           | -0.100       | 0.000          | 0.25           |                   |                | 10.9          |        | OK                |
| 1.011 | S11           | -0.237       | 0.000          | 0.10           |                   |                | 13.5          |        | OK                |

RSK LDE

Page 13

18 Frogmore Road  
Hemel Hempstead  
Hertfordshire HP3 9RT

Date 20/07/2023 16:56  
File 134285\_ SW NETWORK 1\_RE...

XP Solutions

West Hoathly Brickworks  
Sharpthorne  
Network 1 SW Calculation

Designed by AMuthusami  
Checked by

Network 2020.1.3

Micro  
Drainage

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 3

Simulation Criteria

Areal Reduction Factor 1.000      Additional Flow - % of Total Flow 0.000  
Hot Start (mins) 0      MADD Factor \* 10m³/ha Storage 2.000  
Hot Start Level (mm) 0      Inlet Coefficient 0.800  
Manhole Headloss Coeff (Global) 0.500      Flow per Person per Day (l/per/day) 0.000  
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0      Number of Storage Structures 5  
Number of Online Controls 0      Number of Time/Area Diagrams 0  
Number of Offline Controls 0      Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model      FSR      Ratio R 0.400  
Region England and Wales Cv (Summer) 0.750  
M5-60 (mm)      20.000 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 450.0  
Analysis Timestep 2.5 Second Increment (Extended)  
DTS Status OFF  
DVD Status ON  
Inertia Status ON

Profile(s) Summer and Winter  
Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440  
Return Period(s) (years) 1, 30, 100  
Climate Change (%) 0, 35, 45

Water  
Level  
(m)

PN

US/MH  
Name

Storm

Return  
Period

Climate  
Change

First (X)  
Surcharge

First (Y)  
Flood

First (Z)  
Overflow

Overflow  
Act.

1.000

S62

1440 Winter

100

+45%

117.263

1.001

S77

1440 Winter

100

+45%

117.055

1.002

S1

1440 Winter

100

+45%

116.606

1.003

S2

1440 Winter

100

+45%

115.884

1.004

S3

1440 Winter

100

+45%

115.426

1.005

S5

1440 Winter

100

+45%

115.321

1.006

S6

1440 Winter

100

+45%

115.224

1.007

S7

1440 Winter

100

+45%

115.087

1.008

S8

1440 Winter

100

+45%

114.906

1.009

S9

1440 Winter

100

+45%

114.787

1.010

S10

1440 Winter

100

+45%

114.645

2.000

S63

30 Winter

100

+45%

119.137

2.001

S64

30 Winter

100

+45%

100/15 Winter

119.122

2.002

S65

30 Winter

100

+45%

100/15 Summer

119.092

2.003

S66

30 Winter

100

+45%

30/15 Winter

119.044

2.004

S67

30 Winter

100

+45%

118.894

2.005

S68

30 Winter

100

+45%

118.706

1.011

S11

120 Winter

100

+45%

114.524

©1982-2020 Innovyze

|                                                              |                                                                    |                                                                                     |
|--------------------------------------------------------------|--------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| RSK LDE                                                      |                                                                    | Page 14                                                                             |
| 18 Frogmore Road<br>Hemel Hempstead<br>Hertfordshire HP3 9RT | West Hoathly Brickworks<br>Sharpthorne<br>Network 1 SW Calculation |  |
| Date 20/07/2023 16:56<br>File 134285_ SW NETWORK 1_RE...     | Designed by AMuthusami<br>Checked by                               |                                                                                     |
| XP Solutions                                                 | Network 2020.1.3                                                   |                                                                                     |

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 3

| PN    | US/MH<br>Name | Surcharged Flooded |                | Flow / Overflow<br>Cap. (l/s) | Half Drain<br>Time (mins) | Pipe<br>Flow (l/s) | Status     | Level<br>Exceeded |
|-------|---------------|--------------------|----------------|-------------------------------|---------------------------|--------------------|------------|-------------------|
|       |               | Depth<br>(m)       | Volume<br>(m³) |                               |                           |                    |            |                   |
| 1.000 | S62           | -0.007             | 0.000          | 1.00                          |                           | 12.4               | OK         |                   |
| 1.001 | S77           | -0.245             | 0.000          | 0.08                          |                           | 12.4               | OK         |                   |
| 1.002 | S1            | -0.244             | 0.000          | 0.08                          |                           | 12.4               | OK         |                   |
| 1.003 | S2            | -0.236             | 0.000          | 0.10                          |                           | 12.4               | OK         |                   |
| 1.004 | S3            | -0.224             | 0.000          | 0.15                          |                           | 12.4               | OK         |                   |
| 1.005 | S5            | -0.209             | 0.000          | 0.20                          |                           | 12.4               | OK         |                   |
| 1.006 | S6            | -0.211             | 0.000          | 0.19                          |                           | 12.4               | OK         |                   |
| 1.007 | S7            | -0.233             | 0.000          | 0.11                          |                           | 12.4               | OK         |                   |
| 1.008 | S8            | -0.224             | 0.000          | 0.15                          |                           | 12.4               | OK         |                   |
| 1.009 | S9            | -0.223             | 0.000          | 0.15                          |                           | 12.4               | OK         |                   |
| 1.010 | S10           | -0.225             | 0.000          | 0.14                          |                           | 12.4               | OK         |                   |
| 2.000 | S63           | -0.013             | 0.000          | 0.52                          | 15                        | 4.8                | FLOOD RISK |                   |
| 2.001 | S64           | 0.022              | 0.000          | 0.81                          | 17                        | 6.9                | FLOOD RISK |                   |
| 2.002 | S65           | 0.042              | 0.000          | 1.02                          | 20                        | 9.6                | FLOOD RISK |                   |
| 2.003 | S66           | 0.044              | 0.000          | 1.42                          | 21                        | 13.2               | FLOOD RISK |                   |
| 2.004 | S67           | -0.056             | 0.000          | 0.72                          |                           | 13.2               | FLOOD RISK |                   |
| 2.005 | S68           | -0.094             | 0.000          | 0.30                          |                           | 13.2               | OK         |                   |
| 1.011 | S11           | -0.228             | 0.000          | 0.13                          |                           | 18.5               | OK         |                   |