



Note:

- Refer to Technical Details, Planting Dwgs and Plant Schedules for location and plant species.
- When preparing the tree pit contractor to check and match tree pit depth with specific tree root balls.
 - Soiling levels to be reduced / brought up to levels required to achieve the planting depths specified.
 - Backfill topsoil in layers not exceeding 300mm and lightly 'settled' rather than compacted between layers.
 - Final tree positions to be marked out on site by the landscape architect / CA.
 - Tree pits to have base and sides broken up / scarified by hand forking.
 - Do not over excavate as it will make soil over porous.
 - Pits to be water tested to ensure that they are free draining. Contractor to photograph each exposed pit and video water test.
 - Trees & shrubs to be mulched with 75mm depth of Melcourt 'Ornamental Grade Bark Mulch'.
 - All areas of soiling to be treated, stripped and cleared of existing grass prior to soiling works.
 - All pits shall be at least twice the spread of the rootball and with a minimum size of 1200x1200mm and where necessary the depth shall be increased to accommodate the depth of the roots, obtaining the correct planting level and appropriate planting conditions.
 - All works to be in strict accordance with Allen Scott Specification for Landscape Works.
 - Any areas of soft damaged by works to be de-compacted and re-turfed by contractor.
 - All services to be identified on site prior to excavations.
 - All planting to be derived from the nominated nursery.
 - All planting to be set out with LA on site prior to planting. Give min 1 weeks notice prior to plant stock arriving on site.
 - All plants must be well watered in directly after planting and mulched.
 - Contractor must monitor soil moisture & plant conditions closely after planting & during maintenance to ensure that a watering regime is established quickly & diligently as soon as soil / plants show signs of drying out / stress.
 - gRootBarrier 325 root barrier to be installed in planting pits adjacent to existing and proposed underground utilities.
 - All planting to be maintained by contractor for a min of 12months post practical completion of all works

LEGEND

- Site boundary
- Original layout removed
- Retained layout
- Proposed layout / edges
- Existing trees to be retained
- Existing trees to be removed above ground & stump ground and area reinstated with seed
- Existing planting to be retained
- Existing areas of grass to be retained
- Soiling - New Areas of Planting**
 - Remove existing soil and stockpile on site (TBA with CA) for re-use on site for making good / reinstatement.
 - Thoroughly break up existing substrate
 - Backfill with 400mm depth of imported topsoil (Bourne Amenity TS1).
- Soiling - Areas to be Reinstated / Improved prior to seeding / turfing**
 - Areas of existing grass adjacent to new works to be reinstated / made good.
 - Bring up levels as required to align with new path levels using site won topsoil.
 - Decompact, cultivate and stone pick existing topsoil to 150mm depth
 - Rake to a true, even consolidated surface ready for meadow seeding
- Soiling - Areas of Hardstanding to be reinstated as grass**
 - Areas previously cleared (see clearance plans)
 - Break up existing substrate
 - Bring up levels to suit existing using site won soil
 - Area previously stripped and cleared of vegetation
 - Decompact, cultivate and stone pick existing topsoil to 150mm depth
 - Rake to a true, even consolidated surface ready for meadow seeding
- 1.2 x 1.2 x 0.8m depth - Tree Pit**
 - Backfill with imported topsoil (Bourne Amenity TS1), over 200mm depth drainage layer at base of pit of clean coarse, angular gravel particle size 20-30mm (Refer to Tree Pit Planting Detail)
- 0.8 wide x 0.6m depth - Hedge Planting Trench**
 - Backfill with imported topsoil (Bourne Amenity TS1), over 200mm depth course washed sand drainage layer. (Refer to Tree Pit Planting Detail)
- gRootBarrier 325 root barrier to be installed in planting pits adjacent to existing and proposed underground utilities. For costing purposes allow 2m per tree pit

Tree Pit Size	Irrigation kit	Anchoring
1.2 x 1.2m	MRSA3*	RF2P**
2 x 2m	MRSA4*	RF3P**

* Green Tech - Mona Relief system
**Platipus Rootball fixing system

NOTES

This drawing is Copyright and shall not be produced nor used for any other purpose without the written permission of the Landscape Architects.
Do not scale from this drawing.
The Contractor is responsible for checking all dimensions on site and report any discrepancies, errors or omissions to the Landscape Architects immediately.
The Contractor shall ensure that all goods, materials and workmanship conform with current British Agreement Certificates, British Standards and Building Regulations, and ensure that all works are executed in full compliance with all current Codes of Practice and Regulations in respect of Health & Safety.

A 17-12-24 JP Proposed trees south of lodge revised further south. JP

Rev Date By Description Ckd



Drawing Status

For Planning

Project: Mount Noddy Park

Drawing Title: Soiling Plan - Site

Client: Mid Sussex District Council

Scale: 1: 500 @ A2 Job No.: 23-739

Date: 13.06.23 Drawing No.: 740-450