



NOT FOR CONSTRUCTION


TO BE READ IN CONJUNCTION WITH
STRUCTURAL ENGINEER'S DRAWINGS,
DETAILS AND SPECIFICATIONS




SOUTH SECTION ELEVATION - THROUGH COURTYARD - AS PROPOSED
SCALE @ 1:50 ON AN A1 SHEET




NORTH SECTION ELEVATION - THROUGH COURTYARD - AS PROPOSED
SCALE @ 1:50 ON AN A1 SHEET




OUTBUILDING 2 EAST
ELEVATION - AS PROPOSED
SCALE @ 1:50 ON AN A1 SHEET



OUTBUILDING 2 NORTH
ELEVATION - AS PROPOSED
SCALE @ 1:50 ON AN A1 SHEET



OUTBUILDING 2 WEST
ELEVATION - AS PROPOSED
SCALE @ 1:50 ON AN A1 SHEET



OUTBUILDING 2 SOUTH
ELEVATION - AS PROPOSED
SCALE @ 1:50 ON AN A1 SHEET

- Elevation Key:
- Red dashed lines denote demolitions
 - Solid red/brown hatch denotes re-bedded ridge tiles
- Existing timber barge boards to be repaired and repainted in white to match the existing
 - Existing sliding sash window to be repaired and upgraded, with new double-glazed panes and draught seals to be installed. To be painted white to match the existing
 - Existing bay window and roof over to be repaired and upgraded - new double-glazed panes and draught seals to be installed, replacement shiplap timber cladding boards, and replacement lead roof. All joinery painted white to match the existing
 - Existing casement window to be repaired and upgraded, with new double-glazed panes and draught seals to be installed. To be painted white to match the existing
 - Existing cast iron rainwater goods to be removed, and replaced with new cast metal rainwater goods with a black powder-coated finish
 - Existing plastic rainwater goods to be removed, and replaced with new black plastic rainwater goods
 - Existing sliding sash window to be repaired and upgraded, with new double-glazed panes and draught seals to be installed. To be painted white to match the existing
 - Existing timber fascia and soffit boards to be repaired and repainted in white to match the existing
 - Existing casement window to be replaced in timber frames with double-glazed panes and draught strips installed. To be painted white to match existing
 - Existing metal framed windows to be repaired and repainted. Existing single-glazed panes to be retained. All existing timber sub-frames/brackets to be repaired and repainted in white to match existing
 - New lead valley to be formed between existing (currently concealed) tiled roof, and boundary wall
 - Existing sliding sash window to be replaced in timber frames with double-glazed panes and draught strips installed. To be painted white to match existing
 - Existing cast iron SVP to be replaced with new cast metal pipe with a black powder-coated finish. Pipe to be fitted with a traditional cowl to prevent vermin ingress
 - Existing dormer window to be repaired and upgraded, existing cheek wall cladding removed, and replacement lead dressing. Replacement double-glazed sliding sash window in timber frame to be installed. All joinery painted white to match the existing
 - Existing timber windows to be repaired and repainted in white to match existing
 - Clean chimney stack brickwork with stiff brush and soap/water, and remove vegetation growth
 - Replace sand/cement fillet weathering details with Code 4 lead flashings
 - Clean elevation brickwork using a stiff brush and soap/water. Allow for localised repointing, in lime mortar
 - Existing shop window canopy to be replaced in Code 4 lead with traditional mopstick roll details
 - Profiled metal roof sheeting with a dark powder-coated finish, to replace existing asbestos sheets
 - Existing timber cladding to be repaired, and repainted to match the timber joinery elsewhere
 - Repairs to existing tiled roofs, with slipped tiles re-fixed, and missing tiles replaced (to match existing)

A	09.09.25	RH	Key notes updated	*
REV.	DATE.	BY.	AMENDMENT.	CHK.

PLANNING



2 Lucastes Mews, Paddockhall Road,
Haywards Heath,
West Sussex, RH16 1HE
(01444) 452604
hb@gouldbaxter.co.uk
www.gouldbaxter.co.uk

NOTES:
DO NOT SCALE OFF THIS DRAWING UNLESS FOR PLANNING PURPOSES.
CHECK ALL DIMENSIONS ON SITE BEFORE ANY WORK IS COMMENCED.
ALL GOODS MATERIALS AND WORKMANSHIP MUST CONFORM WITH
CURRENT BUILDING REGULATIONS, BRITISH STANDARDS AND CODES OF
PRACTICE.
COPYRIGHT OF THIS DRAWING IS RETAINED BY GOULD PROPERTY
CONSULTANTS LLP T/A GOULD BAXTER AND IT MUST NOT BE REPRODUCED
WITHOUT WRITTEN CONSENT.

CLIENT:
Mr. & Mrs. R. Shepherd

PROJECT:
83 High Street
Lindfield, West Sussex
RH16 2HN

DRAWING:
Sectional Elevations, and Outbuilding
2 Elevations - As Proposed

DATE: 18.07.2025	SCALE AT A1: 1:50	DRAWN BY: RH CHECKED BY: MC
---------------------	----------------------	--------------------------------

JOB NO. GH941	DRAWING NO. PL.005	REV. A
------------------	-----------------------	-----------

