








TOTAL VOLUME = $15.40 + 32.81 = 48.21m^3$



- PERMITTED DEVELOPMENT CRITERIA FOR LOFT CONVERSION
- * VOLUME OF DORMER & HIP TO GABLE DOES NOT TO EXCEED 50CUBM
 - * REAR DORMER WALL TO BE SET UP ROOF SLOPE MIN 200mm
 - * NEW EXTERNAL MATERIALS TO MATCH WITH EXISTING
 - * NO PART OF THE NEW WORK TO EXCEED THE RIDGE HEIGHT NOR ENCROACH THE BOUNDARIES
 - * ROOF WINDOWS ON FRONT SLOPE NOT TO PROJECT MORE THAN 150mm BEYOND THE SURFACE OF THE ROOF COVERING
 - * ANY SIDE WINDOW TO BE FIXED SHUT & GLAZED WITH OBSCURE GLASS BELOW A HEIGHT OF 1.7m FROM THE ADJACENT FINISHED FLOOR LEVEL

 TheHarvest Partnership Design, Construction, Planning, & Development Consultants Tel: 020 8253 7110 Fax: 020 8253 7111 www.harvestpartnership.co.uk email: info@harvestpartnership.co.uk Apex House 41 Tamworth Road Clayton CR0 1XU			
Proposals	Address		
LOFT CONVERSION	4 KING GEORGE AVE EAST GRINSTEAD SURREY RH19 2AS		
Title	Client		
PROPOSED ARRANGEMENTS	Mr RIVERS & Miss RANSOM		
Drawing No	Scale	Revision	Date
O2	1:50		NOV 2024